

EHDESIGN.COM

### SUN PRAIRIE PUBLIC LIBRARY

SUN PRAIRIE, WISCONSIN SCHEMATIC DESIGN BOOKLET 4 SEPTEMBER 2023





# **PROJECT DIRECTORY**

### Sun Prairie Public Library

1350 Linnerud Drive Sun Prairie, WI 53115 Svetha Hetzler – Library Director Kevin Johnson – Owner's Representative (FVM/Hunzinger)

# FEH Design

1241 Corporate Center Drive Oconomowoc, WI 53590

Christy Monk	Principal in Charge	563 583 4900
Kim Bellmann	Architect	563 583 4900
Brady Ludvik	Architectural Designer	262 968 2055
Bryan Blair	Structural Engineer	563 583 4900
Elliot Carlovsky	Structural Designer	563 583 4900
Sarah Jansen	Interior Designer	262 968 2055
Ellie Wigginton	Interior Designer	563 583 4900

# Snyder & Associates

5010 Voges Road Madison, WI 53718

Scott Anderson	Civil Engineer	608 838 0444
Andy Meessmann	Landscape Architect	608 838 0444

### **Design Engineers**

8215 Greenway Blvd, Suite 180 Middleton, WI 53562

Brad Biddick	Senior Electrical Consultant	608 424 8815
Allison Clemens	Mechanical Project Engineer	608 424 8815

# TABLE OF CONTENTS

- 1. Authorization to Proceed
- 2. Goals for Success
- 3. Space Needs Summary
- 4. Architectural Narrative
- 5. Structural Narrative
- 6. Site Narrative
- 7. Engineering Systems Narrative
- 8. Budget Opinion
- 9. Project Timeline
- 10. Meeting Minutes
- 11. Drawing Set
  - a. Title Sheet
  - b. General Notes and Legends
  - c. Building Code Plan
  - d. Existing Site & Demo Plan
  - e. Proposed Site
  - f. Grading Plan
  - g. Utility Plan
  - h. Planting Plan
  - i. Hardscape Plans
  - j. Demolition Plans
  - k. Floor Plan
  - . Roof Plan
  - m. Exterior Elevations
  - n. Building Sections
  - o. Interior Views
  - p. Reflected Ceiling Plan
  - q. Furniture Layout Plan
  - r. HVAC Equipment Layouts
  - s. Electrical Schematic



# **Authorization to Proceed**

The undersigned representative for the Sun Prairie Public Library, acknowledges that the Schematic Design Documents, as compiled and attached hereto, have been received as complete and accurate, and authorize proceeding into the Design Development phase for the project.

Signature:

Date:







# GOALS FOR SUCCESS

- Ensure that we serve the community needs for the next 20 years
- Grow with Sun Prairie socio- economic needs
- Improve infrastructure for comfort, aesthetics, safety, and security
- Tie core values to physical space to reflect culture
- Provide adequate space to support collections and programs
- Consider flexible indoor spaces
- Include outdoor spaces
- Include collaborative Makerspace with the Sun Prairie Media Center
- Include space for Foundation Executive Director
- Include storage space
- Remove barriers to serve all members of our community
- Provide more flexible and equitable access
- Enhance the drive up window to serve patrons
- Be good stewards of financial, environmental, and cultural sustainability
- Ensure the Library is an essential destination
- Promote and foster life-long learning and creativity
- Create an environment that continues to be comfortable
- Maintain current integrity of our "GEM" inside and outside
- Create opportunities for exposure to local and national art
- Facilitate communication using technology
- Provide broad and diverse collection access for the community

# EXCERPT FROM SPACE NEEDS SUMMARY

# SUN PRAIRIE PUBLIC LIBRARY SPACE NEEDS SUMMARY

	Sq.ft.
ENTRY ARCADE / ATRIUM	5,900
WELCOME + ORIENTATION	4,809
ADULT SERVICES "THE HUB"	1,288
ADULT SERVICES FICTION	5,262
ADULT SERVICES MEDIA	1,307
ADULT SERVICES NONFICTION	5,703
ADULT SERVICES DIGITAL	1,485
MAKER SPACE	2,316
TEEN SERVICES	3,495
YOUTH SERVICES CENTRAL	4,251
YOUTH SERVICES PRESCHOOL ZONE	5,023
YOUTH SERVICES GRADE SCHOOL.ZONE	3,417
MEETING ROOMS	3,366
STAFF ADMINISTRATION	704
STAFF TECHNICAL SERVICES	1,562
STAFF NETWORK SERVICES	754
STAFF MAINTENANCE	253
STAFF OTHER	1,210
FRIENDS OF THE LIBRARY	1,089
SUN PRAIRIE MEDIA CENTER (SP.MC.)	2,807
DESIGNATED NONASSIGNABLE	2,502
Sum of all department totals	58,500
Nonassignable / mech @ 5% of gross	3,441
Nonassignable / other @ 10% of gross	6,882
GROSS AREA NEEDED	68,823
v1.0 69,314 Renovate existing	36,100
v1.1 69,124 Addition	23,000
v1.2 68,513 Arcade / atrium	5,900
v1.3 68,823	65,000
▶105%	68,250
110%	71,500



# EXCERPT FROM SPACE NEEDS SUMMARY

### SUN PRAIRIE PUBLIC LIBRARY SPACE NEEDS SUMMARY

ENTRY ARCADE / ATRIUM	Sq.ft.
Arcade / atrium	
DEPARTMENT TOTAL	5,900

WELCOME + ORIENTATION	Sq.ft
Traffic dispersal	390
Customer service. desk. /. greeter	150
Customer service. desk. /. circulation .+. entry. (."Ask." desk)	450
Self-service center.	590
Interior walk-up materials return	250
Circulation department workroom.w AMH	1,155
Circulation department storage room	110
Circulation department "ready. room"	120
Drive-up materials return. (roomlet).	120
Drive-up service.window	100
ASSIGNABLE SPACE IN DEPT	3,435
Nonassign allow (@ 10% of assign)	344
Allowance for entry vestibule./ meeting lobby	250
Allowance for public restrooms	780
DEPARTMENT TOTAL	4,809

ADULT SERVICES "THE HUB"	Sq.ft
Customer service. desk. /. adult	441
Adult services department .workroom	500
Adult services department storage room	110
Adult services department."ready room"	120
ASSIGNABLE SPACE IN DEPT	1,171
Nonassign allow (@ 10% of assign)	117
DEPARTMENT TOTAL	1.288

ADULT SERVICES FICTION	Sq.ft
Browsing / new.books including.fresh reads.+ .seating	616
Browsing / magazines.+ newspapers.+ seating	(
Fiction collection + seating	3,092

Graphic novels collection			•
Large print collection +.seating	•		
ASSIGNABLE SPACE IN DEPT			
Nonassign allow (@ 10% of assign)			
DEPARTMENT TOTAL			

#### **ADULT SERVICES -- MEDIA**

Browsing / new.nonprint				
Audio collection				
Video collection				
ASSIGNABLE SPACE IN DEPT				
Nonassign allow (@ $10\%$ of assign)	)			
DEPARTMENT TOTAL				

#### **ADULT SERVICES -- NONFICTION**

Nonfiction collection. + seating				
Local history collection +.seating.(Renk.Room)				
Quiet reading room. /. area				
Small group study rooms				
ASSIGNABLE SPACE IN DEPT				
Nonassign allow ( $@$ 10% of assign)				
DEPARTMENT TOTAL		•		

#### ADULT SERVICES -- DIGITAL

Technology hub	
Business center	
ASSIGNABLE SPACE IN DEPT	
Nonassign allow (@ 10% of assign)	
DEPARTMENT TOTAL.	

# MAKER SPACE

Maker lab (room)			
Maker lab storage.room			
ASSIGNABLE SPACE IN DEPT		 •	
Nonassign allow ( $@$ 10% of assign)		 •	
DEPARTMENT TOTAL			

							177
							899
							4,784
						•	478
						•	5,262

								Sq.ft.
								120
								513
								555
								1,188
								119
							•	1,307

Sq.ft.						
3,360		 •				
1,165						
0						
660						
5,185						
518						
5,703						

								Sq.ft.
								1,020
•								330
							•	1,350
•								135
	•							1,485

							Sq.ft.
							1,920
							185
							2,105
•							211
							2,316

TEEN SERVICES	Sq.ft.
Customer service. desk. /. teens	235
Teen tech zone	255
Teen collection +.seating	2,237
Teen gaming zone	130
Teen small group study rooms	320
ASSIGNABLE SPACE IN DEPT	3,177
Nonassign allow (@ 10% of assign)	318
DEPARTMENT TOTAL	3,495

YOUTH SERVICES CENTRAL	Sq.ft.
Customer service. desk. / youth	670
Youth tech zone	730
Nonprint collectian	576
Parenting collection +. seating	116
Youth services dept.workraam	1,160
Youth services dept storage room	220
Youth services department. ".ready room"	120
ASSIGNABLE SPACE IN DEPT	3,592
Nonassign allow (@ 10% of assign)	359
Allowance for children's restrooms	150
Allwance for caregiver's room	75
Allowance for sensory room	75
DEPARTMENT TOTAL	4,251

YOUTH SERVICES PRESCHOOL ZONE	Sq.ft
Board books + seating	345
Picture books + seating	1,857
Readers + seating	454
Discovery zone	500
Children's program./. storytime room	1,120
Storytime storage room	290
ASSIGNABLE SPACE IN DEPT	4,566
Nonassign allow (@ 10% of assign)	457
DEPARTMENT TOTAL	5,023

YOUTH SERVICES GRADE SCHOOL ZONE	Sq.ft.
Grade school fiction +.seating	1,474
Grade school nonfiction .+. seating	1,292

Small group study rooms	
ASSIGNABLE SPACE IN DEPT	
Nonassign allow (@ 10% of assign) $\dots$	
DEPARTMENT TOTAL	

#### MEETING ROOMS

Multi-purpose room
Kitchenette (room)
Table + chair storage room.
Equipment storage room.
Conference room
Multi-purpose room 2
ASSIGNABLE SPACE IN DEPT
Nonassign allow (@ 10% of assign) $\ldots$
DEPARTMENT TOTAL

#### **STAFF -- ADMINISTRATION**

Director's office
Foundation office
Administrative ".ready room"
Friends office
Huddle room 1
Huddle room 2
Records archive (room).
ASSIGNABLE SPACE IN DEPT
Nonassign allow (@ 10% of assign)
DEPARTMENT TOTAL

Technical services.dept.workroam	
Technical services.dept.storage.room	
ASSIGNABLE SPACE IN DEPT	
Nonassign allow (@ 10% of assign) .	
DEPARTMENT TOTAL.	

#### STAFF --- NETWORK SERVICES

$Network\ services.\ dept.\ warkroom\ .\ .$			•				•		
Network services. dept. storage.room									

											3	40	)
										3	,1	06	5
											3	11	1
						•				3	,4	17	7

										Sq.ft.
										1,540
										120
										200
										120
										620
										460
										3,060
										306
•										3,366

								Sq.ft.
								130
								130
								120
								0
								120
								0
								140
								640
								64
								704

									Sq.ft.
									1,315
									105
									1,420
									142
									1,562

											Sq.ft.
											280
•		•	•		•	•	•	•			165

Server farm (room)	120
Network closet (roomlet).	120
ASSIGNABLE SPACE IN DEPT	685
Nonassign allow (@ 10% of assign)	69
DEPARTMENT TOTAL	754

STAFF MAINTENANCE	Sq.ft
Maintenance office	(
Maintenance office.+ shop (room)	230
ASSIGNABLE SPACE IN DEPT	230
Nonassign allow (@ 10% of assign)	23
DEPARTMENT TOTAL	253

STAFF OTHER	Sq.ft.
Staff copy center (room)	230
Staff mail room	200
Staff break room	465
ASSIGNABLE SPACE IN DEPT	895
Nonassign allow (@ 10% of assign)	90
Allowance for staff wellness room	75
Allowance for staff restrooms	150
DEPARTMENT TOTAL	1,210

FRIENDS OF THE LIBRARY	Sq.ft.
Read Before Book.Stare	600
Move Friends office.here?	0
Friends receiving and sorting.(room)	390
ASSIGNABLE SPACE IN DEPT	990
Nonassign allow (@ 10% of assign)	99
DEPARTMENT TOTAL	1,089

SUN PRAIRIE MEDIA CENTER (SPMC)	Sq.ft.
Reception	150
SPMC Director's office	90
Staff work space	360
Technology room	120
Radio studio (room)	90
Large studio (room)	865

Control room 1					•				
Small studio (room)									
Control room 2									
Storage room									
ASSIGNABLE SPACE IN DEPT									
Nonassign allow (@ 10% of assign)									
Allowance for SPMC restroom									
DEPARTMENT TOTAL					•	•			

#### DESIGNATED NONASSIGNABLE

Receiving & delivery (room)	
Staff entry (room).	
Storage roomgeneral supplies.and.misc	
Storage roomoffice supplies	
Storage roommaintenance.supplies	
Recycling center.(raom)	
Groundskeeping.equipment room	
Janitor's closet (raom)	
ASSIGNABLE SPACE IN DEPT	
Nonassign allow (@ 10% of assign)	
Allowance for garaage	
DEPARTMENT TOTAL	
Sum of all department totals	
Nonassign / mech 🤄 5% of gross	
Nonassign / other @ 10% of gross	
GROSS AREA NEEDED.	

								95
								360
								95
								190
								2,415
								242
								150
		•		•	•		•	2,807

								Sq.ft.
								460
								100
								240
								120
								180
								120
								300
								300
								1,820
								182
								500
								2,502
								58,500
								3,441
								6,882
								68,823

# **ARCHITECTURAL NARRATIVE**

### Architectural Existing Conditions

The 1998 Sun Prairie Public Library is one story, slab on grade 35,692 GSF building comprised of metal stud framing with masonry veneer in brick, stone, and limestone. Continuous gable roof forms intersect to create an open, vaulted interior aesthetic with low-slope roof quadrants to house mechanical equipment. Porches are located on the west and east ends of the building. A portion of the building's northeast corner is occupied by the Sun Prairie Media Center; this is an acoustically separated space.

The exterior of the building is primarily constructed of brick, stone, and limestone veneers. The main entrance is on-grade centered on the south façade. Entrances on the west and east are provided for staff and the media center, respectively.

The existing roof is a mix of forms and materials. The gables are asphalt shingles, cement tile roofing, copper standing seam roofing, with copper flashing and stone copings. The low slope roof quadrants that house mechanical equipment are covered with black EPDM roof membrane.

The porches provided on the west and east sides of the building have cedar siding and a cedartrimmed fascia.

### Proposed Addition and Renovation

The proposed building addition is 22,085 square feet on one level, to the east of the existing building. A 2,830 SF atrium along a portion of the north face of the existing building and addition will provide a lobby and pre-function space. The atrium will also provide a connection from the expanded, east parking lot to the library entrance. The building addition extends approximately 155-feet from the east face of the existing building.

The addition will house the youth services, teen, and makerspace elements. The existing building will house the adult collection, large meeting room space, and the majority of the staff spaces. The Read Before Book Store will remain in its original location with additional space and expanded beverage offerings. The current library entrance will remain, and the main staff 'ask' desk will be located at the N/S and E/W gable ceiling intersection. This will allow for ease of supervision, wayfinding, and a visual connection between the three primary staff points. The existing staff entrance will be reworked to provide ease of use for patrons utilizing the book drop / pick up windows and safety for staff. The west porch will be removed and a carport for a library vehicle will be provided.

The adult collection will have expanded shelving, more diverse seating options, study rooms of different sizes, and a dedicated computer area with a staff desk that has visibility to the ask desk.

The Renk Room will be retained as a quiet reading space with expanded functionality to include small meetings.

The makerspace will be adjacent to and accessible by the Sun Prairie Media Center. The makerspace will house a video recording studio, a voice recording studio, digital editing computers on the north portion. The south of the room will have tables and seating for crafts, education, and making. A portable kitchen will also be provided in this space.

The youth area will have access to an outdoor patio space, a dedicated program room, expanded collection space, and a variety of seating and technology options for kids and parents. The youth service desk and staff space will be located at the east-most point of the E/W building axis.

The teens will have a dedicated, enclosed space for gathering, gaming, and reading. This will be accessed from the youth space. An exterior door to the patio will be provided from the teen space.

The existing building will receive new finishes (carpet, ceiling tile, paint) but will remain intact. The addition will have a complementary feel to the existing, but not replicate the original building.

An outdoor amphitheater will be constructed in the southeast corner of the addition, with access from the expanded parking lot and the building addition. The amphitheater will have an open air bandshell. A toilet room will be provided off the patio.

Building code updates will be made to the overall building as part of the expansion. Fire separations and exiting will be updated; the addition will be separated from the existing building by a 1-hour fire separation. Accessibility items will be replaced and upgraded where appropriate.

A priority has been set for LEED Gold building certification. This will be accomplished through selection of materials, finishes, and reuse of elements (where applicable). The project will also incorporate construction waste management strategies. Daylighting, user comfort, and efficient building systems will be part of the overall design.



# STRUCTURAL NARRATIVE

### Proposed Structural System

The new library addition will be a one-story, steel brace framed structure, constructed off of the east elevation of the existing public library. The roof framing will be metal deck supported by open web steel joists and steel beam framing at steel tube column lines. Exterior walls will be steel frame with non-load bearing exterior cold formed infill stud and a masonry veneer. The structural frame will be supported on piers and isolated spread footings at steel tube columns, and on continuous concrete stem-walls with continuous spread footings at exterior walls.

There will be a separate amphitheater structure to the southeast of the addition that is to be constructed from steel tube columns supporting glulam beams and a tongue and groove decking system. Steel columns will bear on isolated footings on piers down past frost.

Typical first story floor will be slab on grade over prepared sub-base, reinforced with synthetic macro-fibers.

Lateral resistance will be achieved using steel braced frames located in select walls throughout the building.

Subgrade below footings and slab will be prepared as recommended by the geotechnical engineer.

# SITE NARRATIVE

### **Existing Site**

The existing site consists of two lots both owned by the City of Sun Prairie. Both lots combine for over 14 acres of area. The site is bound by residential to the west and north, Linnerud Drive to the south and vacant land to the east that is a community garden. Mature trees line Linnerud Drive with established native prairie in front of the library.

### **Proposed Site**

The proposed site will consist of the existing 7.1 acres and adjacent land to the east to accommodate the building expansion and the new parking lot. The existing drive lane will be widened for easier access. An outside patio will be located on the east side of the building with a new amphitheater in the southeast corner. Sidewalks, drop off areas, and pathways have been integrated into the site.

### Utilities

Information from the MEP designers have indicated that the existing water can be utilized for fire protection and domestic service. The new building addition will be served by a new sanitary sewer lateral that will need to be extended from within the Linnerud roadway. Storm sewer will be provided throughout the exterior patios and parking lot to direct the stormwater to the east to the bioretention area.

### Stormwater Management

Stormwater Management will be provided by a large bioretention area located to the east of the parking lot and building expansion. The bioretention area will utilize infiltration and native plantings to treat the stormwater. This will complement the existing scheme of the native prairie that the library has on display on the grounds today. The pond will discharge to the existing drainage ditch where the water currently goes.

### Landscaping

Landscape space will include an updated entry plaza at the northern portion of the building that unites the existing entrance with the new proposed (east) entrance. The entry plaza will include gentle curves that lead visitors to the east patio space. A sidewalk along the east of the building will include a "story walk" that runs south into the proposed amphitheater space. The amphitheater will be surrounded by taller evergreens to provide shade and comfort for daytime activities. A walk along Linnerud drive will be revised to pass near the existing art sculpture on the south side of the library and connect to the lower and upper amphitheater space. The route will be fully ADA compliant. Updated landscaping will include native prairie areas with savannah prairie types of trees at the south and eastern portions of the site.

# ENGINEERING SYSTEMS NARRATIVE

### INTRODUCTION

The fundamental goal for the mechanical and electrical systems within this project is to provide system infrastructure that will support the libraries' project goals. The design goal for the project will be to provide a safe, comfortable environment for the users while promoting energy efficiency and maintaining flexibility of systems to accommodate future modifications. The energy goals for the project include steps towards an all-electric building with a minimum goal of achieving LEED Gold status.

# MECHANICAL AND PLUMBING SYSTEMS

### Fire Protection

The existing building sprinkler system will remain in service. The 6" combined domestic water and sprinkler service entrance shall be existing to remain. Per the 2018 facility assessment, the existing system is a dry-type system with an operational compressor, concealed heads, and exposed pendant heads. The issues with below-freezing conditions will be mitigated by the removal of the porches in the renovation. The existing dry-type sprinkler system shall be extended to serve the new addition. New dry-type concealed and exposed pendant heads shall be installed throughout the new addition. The existing compressor size shall be assessed to determine if a larger compressor size is needed to serve the addition. The building does not meet the height requirements to necessitate a standpipe system and it is not anticipated that a fire pump will be necessary. The existing fire department connection shall be existing to remain.

# Heating, Ventilation and Air Conditioning (HVAC) & Indoor Air Quality Design Criteria

Heating, cooling, ventilation, and humidification/dehumidification load calculations will be based on the parameters listed below:

- Exterior design conditions:
  - Summer: 92 F dry bulb, 76 F wet bulb
  - Winter: -20 deg F dry bulb
- Interior design conditions:
  - Summer: 75 F dry bulb, +/- 3 F, 50% relative humidity, +/- 5%
  - Winter: 70 F dry bulb, +/- 3 F, 30% relative humidity, +/- 5%
- Outdoor air flow will be provided in accordance with ventilation as required per ASHRAE 62.1-2016.

- Internal Loads:
  - Lighting
    - 1.20W/sf for library stacks
    - 0.93W/sf for offices
    - 0.82W/sf for reading areas
    - 1.07 W/sf for conference room
  - People
    - 245 Btu per hour sensible; 155 Btu per hour latent

### Air Handling and Distribution Systems

Two new penthouses will be constructed to house central air handling units to serve the collections spaces, offices, and meeting rooms. The east penthouse will house two approximately 20,000 cfm air handling units to serve the northeast and southeast quadrants of the existing building and the addition. The west penthouse will house one approximately 20,000 cfm air handling unit to serve the southwest collections area of the existing building and the staff area. Each air handling unit will consist of a supply fan, hydronic heating and cooling coils, and a return fan.

A total energy recovery unit will be located in the east penthouse to supply fresh air to the two east penthouse air handling units and exhaust air from the restrooms and janitor's closets, providing additional efficiency. The air leaving the ERU will be tempered but not temperature neutral, as it will be further conditioned at each AHU. Humidity control will be provided at the air handling units to modulate overall building humidity and enhance occupant comfort. Each AHU will also be equipped with economizer mode to bring in higher outdoor air volumes for increased efficiency.

New ductwork will be provided for both the existing building and the new addition. Variable air volume terminal units with hot water reheat coils will provide additional zone control and occupant thermal comfort. Offices and study rooms will be zoned separately from higher occupancy spaces. Collections areas will have separate zone controls for the perimeter reading areas and the center stacks areas.



# Hydronic Systems

New high-efficiency, gas-fired hot water boilers, along with heating hot water circulating pumps and all required accessories will be provided. The boilers will supply hot water to the VAV reheat coils, the air handling unit coils, and perimeter heating. It is anticipated that hot water cabinet unit heaters will be provided for building entry vestibules and receiving areas. Perimeter heating in the form of finned tube or radiant ceiling panels will be provided in the front lobby and "atrium" space to offset the higher envelope load from the windows. The existing boilers and underslab radiant heating system in the existing building shall be demolished. The underslab heating piping shall be removed or abandoned underslab.

New air-cooled chillers, along with chilled water pumps and all required accessories, will supply chilled water to the air handling unit coils and fan coil units for server rooms. The central plant will be sized for N + 1 redundancy to allow continual building operation in the event of a component failure.

The hydronic system will be set up such that a future project could be completed to install a groundsource geothermal system and replace the gas-fired boilers and air-cooled chillers with modular water-to-waterheat pump chillers to provide the hot and chilled water to the existing building systems. This future central-plant conversion would allow the building to be net-zero ready.

# **Building Automation System**

A Direct Digital Control building automation system will be provided for control of all new mechanical system components and act as a central hub for water and electrical energy meters. Each zone or area will have individual control and will be addressable at the controller.

It is anticipated that demand control ventilation with CO2 sensors will be provided for the youth program room, collections areas, community room, and other high occupancy spaces. Occupancy control of the heating, cooling and air conditioning systems will be further developed as design progresses.

The community room controls will be tied into the battery storage system to allow continual operation of ventilation to the community room in the event of a power outage.

# Testing and Balancing and Third-Party Commissioning

All new systems will be completely tested and balanced and undergo an HVAC Commissioning process prior to being placed into service.

### Phasing

The existing building rooftop units will remain in service during the construction of the addition. The central plant for chilled and hot water will be installed in the mechanical room in the new addition. The air handling units for the new addition will be operational before the existing rooftop units and boilers are removed from service.

### LEED

The prerequisite LEED items, including Commissioning and Verification, Minimum Energy Performance, Building-Level Energy Metering, Fundamental Refrigerant Management, and Minimum Indoor Air Quality Performance will be completed. Other credits such as renewable energy, thermal comfort, and indoor air quality assessment will be completed as part of the design to achieve LEED Gold. A solar energy analysis will be conducted to determine the potential renewable energy offset available from rooftop solar panel installation.

# Plumbing Systems

The 6" combined domestic water and sprinkler service entrance in the existing building shall be existing to remain. The domestic water supply mains in the existing building are in good condition and shall be increased as required to extend to serve the new addition. The meter size shall be increased to accommodate the added capacity. The water softener for the existing building is past its life expectancy and shall be replaced with a larger water softener to supply softened water to the water heater. The existing building water heater shall be replaced with a high efficiency electric resistance tank style water heater to supply the entire building with hot water. A system of hot water recirculating piping and a pump will be provided to ensure continuous availability of hot water during occupied hours.

Electric water coolers in the existing building are past their useful life and shall be replaced. Existing plumbing fixtures are in good condition per the 2018 facility assessment and shall be existing to remain. New plumbing fixtures shall be added where programming has changed.

The new plumbing fixtures in both the existing building and the addition will be low flow to conserve water. Building water use reduction for LEED will be accomplished through low consumption water closet, urinal, and sink fixtures. It is anticipated that these fixtures will meet the LEED prerequisites, but will not generate enough water savings to qualify for additional credits.

A new gas service shall be brought to the new addition to serve the new boilers. After the existing roof top units and existing boilers have been taken out of service, the existing building gas meter and piping shall be demolished.



The storm system for the existing building is in good condition and shall be existing to remain. Roof drains and storm piping will be provided to serve the new addition. It is anticipated that a separate overflow roof drain system will also be provided that will daylight to splash pads located on grade.

The sanitary system for the existing building is in good condition and shall be existing to remain. A new sanitary main shall be provided to serve the fixtures within the new addition.

# ELECTRICAL SYSTEMS

### Power and Emergency Power Requirements

The existing utility source supplying the 208y/120V, 3 phase, 1200A electrical service will be removed along with the existing utility transformer. The existing main switchboard will be removed. A new 480y/277V, 3 phase service will be approximately 1200A and will provide power to all motors, HVAC equipment, and general lighting throughout the building and the site. The revision to 480V service voltage is primarily to benefit the microgrid connected sources. A new utility transformer will be provided on site which will require new metering.

The electrical service will be configured as a microgrid system integrating utility, photovoltaic and battery energy storage systems. The system will be capable of islanding with the electrical distribution system configured into three tiers of load classifications to allow for shedding strategies to maximize battery runtime. Tier 1 (No Shed) loads will include those essential to grid resiliency and community operations. Tier 2 loads will include those which may be shed to preserve Tier 1 battery supply. Tier 3 loads will be considered non-essential and will be the first to be shed as the battery supply is diminished.

The battery energy storage system (BESS) will be AC connected and located outdoors. The system will be configured to provide peak demand power shaving along with building power when utility sources are unavailable. The BESS will be approximately 50kW and 128kWH rated. The initial sizing will provide up to 4 hours of energy for the total building or 24 hours of energy with Tier 1 loads only.

The photovoltaic (PV) system will be AC connected with PV modules located on the roof of the building addition. The system will be configured to supply the microgrid in both grid connected and islanding modes. The PV system will be approximately 125kW consisting of 275 modules at 450W each.

The main service disconnecting means will be in a microgrid switchboard which serves as a common bus with controllable OCPD for interconnecting sources and loads. Additional coordination is required with Sun Prairie Utilities to determine if the utility main breaker, PV interconnection disconnect and BESS interconnection disconnect will be required to be located on the exterior of the building.

This switchboard will contain the required GFCI protection and arc fault energy reduction controls. The switchboard will have copper bussing, a surge protection device, breakers to feed downstream panels and additional space and spare breakers.

The microgrid control system will be accessible remotely through web-based interface as well as HMI touch screen on microgrid switchboard. The control system will integrate data associated with energy supply and building load. Variables set in the system will determine energy strategies related to peak demand shavings along with battery usage in islanding mode. The microgrid control system will include bi-directional communications with HVAC building automation and lighting control systems.

Distribution panel boards at 480V/3 will be installed in electrical rooms to provide power to all HVAC equipment. In addition, branch circuit panel boards will be installed for all lighting circuits to be served at 277V. A 480:208V transformer will be installed in the main electrical service room to provide power to the 208V distribution system in the building.

The 208V/3 phase distribution in the building will be approximately 1200A and will provide power to all branch circuit panels.

Branch circuit panel boards, at 208V/3, will be installed throughout the facility to feed branch circuits. Panels for offices, corridors, classrooms, and restrooms will be installed in secure areas.

All branch circuits will be monitored and metered with demand information supplied to the energy management system.

An arc flash study and coordination study will be required by the electrical contractor and all labeling of key distribution equipment will be provided by the contractor. Adjustment of breaker settings will be performed by the contractor as specified in the completed study.

Emergency power to egress lighting will be supplied from centralized 3 phase battery inverters. The inverters will be interlocked with the energy management system to supply connected lighting loads when utility power is unavailable.

Electric vehicle charging stations will be provided in the parking lot. They will be connected to the building electrical distribution system and managed by the City/Library. They will be Level 2 type with all required software to manage charging rates and billing. Control of the EVC will be integrated into the building energy management system.



# Lighting

Lighting will be installed to achieve lighting levels in accordance with the requirements of IESNA foot candle levels and ASHRAE Watts/sf for libraries buildings. However, an overall building wide reduction of 30% better than permitted will be attempted.

All lighting will utilize LED sources and be dimmable.

Basis-of-Design Lighting Strategies:

- Stack Areas Suspended direct/indirect lighting
- North addition, Pre-Function Space Mixture of recessed and suspended architectural lighting to support architectural features.
- Conference & Study Rooms Suspended direct/indirect lighting
- Youth Program Room Mixture of recessed and suspended architectural lighting to support fun interior concept.
- Makerspace Recessed direct lighting
- Single and Multi-Occupant Offices, Staff Workrooms Recessed direct lighting
- Storage, Mechanical, Custodial and similar back-of-house areas Lensed strip lighting
- Restrooms Recessed direct lighting with wall mounted vanity lighting

All lighting within the existing library will be replaced. Custom lighting elements within the entry and high ceiling areas may remain with new LED retrofit to improve performance.

Where possible, a combination of occupancy and vacancy sensors will be used to automatically control lighting. Open stack areas and similar spaces will be controlled with a time-based system.

The lighting control system will be integrated into the building energy management system. During periods of peak demand or during islanding mode, lighting may be automatically dimmed to reduce demand on the BESS.

Exterior lighting will be provided at all doors along with architectural lighting on the building. The Amphitheater lighting is TBD. If required, exterior grade performance lighting will be provided with dedicated controls. Parking lot lighting will be replaced and expanding into new parking areas. All exterior lighting will be controlled by an astronomical timeclock as part of the lighting control system.

# **Emergency Lighting**

Emergency and egress lighting will be provided through an emergency lighting inverter and connected to a branch circuit panel. Emergency lighting will be located along paths of egress and areas requiring exit access. Exit signs will be provided per code and supplied with integral batteries.

At exterior egress locations, an exterior mounted path of egress to a safe distance from building.

# ELECTRONICS SAFETY AND SECURITY

# Fire Alarm

The renovation and addition will require a new fire alarm system throughout the facility. The new system will be an Emergency Voice/Alarm type. Initiation and signaling devices will be installed as required by the building code. The system will be interfaced with the fire suppression system. The existing fire alarm system will be removed. System monitoring will be revised to cellular with IP backup.

# Security

It is anticipated that an intrusion detection system and video surveillance system will be required throughout the facility. These systems can be an expansion of any existing standards the City has for other City owned properties. Cameras will be network POE type with network connected video recording system / storage. Video management software will be installed on a local machine for library staff use.

Updated RFID detection gates will be provided at the main library entrance as part of the project.

# Access Control

The Access Control System will be provided at doors requested by the Owner. The system will be an extension of any City standard systems. It is anticipated that the access control system components will be installed within the telecommunications network rooms.

# VOICE, DATA, AND AUDIO/VIDEO SYSTEMS

# **Structured Cabling**

The existing telecommunications room will remain and serve as the main point of distribution (MDF). Intermediate (IDF) telecommunications rooms will be provided in the addition at locations required to supply network cabling to all parts of the building. Backbone fiber optic cabling will be provided between MDF and IDF. All rooms will be provided with telecommunications racks and will be designed in accordance with ANSI standards.

Primary and secondary pathways will be installed per City and South Central Library System standards. Primary pathways are generally 4" conduit sleeves and 12"x4" wire basket in accessible ceiling space or visible in corridors, secondary pathways are minimum 3/4" conduit from the work area outlet to the cable tray (dedicated, no daisy chaining outlets or "teeing" conduits). Primary pathways are for carrying backbone, structured cabling to work area outlets, access control and

### At exterior egress locations, an exterior mounted fixture will be located above door height to illuminate



video surveillance cabling throughout the building. Secondary pathways are for taking individual systems cabling from primary pathway to either the work area outlet or the appropriate field device.

Voice and data services cabling shall be ANSI TIA Cat 6 cable, in a patch panel environment by approved certified installers only. Underground pathways will not be provided in the addition. All fire rated penetrations will be conduit sleeves with EZ-Path system sealants.

Telecommunications grounding and bonding will be provided per ANSI standards.

### Paging

A new paging system will be provided throughout the existing building and addition. The system will be interfaced with the telephone system. Speakers will be ceiling flush mount type with cabling routed free-air above accessible ceilings. The system will be either network/IP type or traditional 70V.

### Audio Visual

Audio Visual systems will be determined during design development phase. Generally speaking, the library will consist of:

- Large Meeting Room A complete divide-combine system with network-based electronics and integration control system.
- Large Conference Rooms A complete standalone system with local electronics and integration control system.
- Study Rooms A complete standalone system with local electronics.
- Children's Program Room A complete standalone system with local electronics.
- Maker Space A complete standalone system with local electronics.
- Digital Signage A complete network-based system with displays located throughout the library.



# **BUDGET OPINION**

OPINION OF PROBABLE COST

Project Number: 2023402	Owner: City of Sun Pr	airie		Date	: 8/29/23	
Phase: Schematic Design	Project: Sun Prairie Public I	ibrary		Estimator :	KE	
					Updated	
					Schematic Design	Conceptual Design
FLITDESIGN					8/29/2023	12/8/2021
DESCRIP	TION	OTY	UNIT	COST/SF	TOTALS	TOTALS
Building Construction Costs:				/-		
1 CENEDAL REQUIDEMENTS 99/ Orandrand 59/ DDOET	7 50/	1	TC		2 442 (17	2 001 751
1 GENERAL REQUIREMENTS 8%, Overnead 5%, PROFIL	. 376	1	LS		2,443,017	2,001,751
2 SITEWORK & UTILITIES & LANDSCAPING 2 SELECTIVE DEMOLITION		1			1,233,920	72,000
SELECTIVE DEMOLITION     SUBSTDUCTURE		1			474.046	72,000
4 SUBSTRUCTURE		1			4/4,940	395,935
6 EXTEDIOD ENCLOSUDE		1			1,507,510	795,000 820,205
7 POOFING		1	LO		701.070	550,000
KOOFING     INTEDIOD CONSTRUCTION		1		>	1 402 771	1.040.870
8 INTERIOR CONSTRUCTION		1	LS		1,495,771	1,040,670
9 SPECIALITES AND EQUIPMENT		1			142,550	125,024
10 CONVERTING STSTEMS		1	LO		127.200	120.000
11 FIRE PROTECTION		1	LS		242,400	225,000
12 PLUMBING		1	LS		243,400	225,000
13 MECHANICAL HVAC		1			5,598,600 2,524,200	2,088,850
14 ELECTRICAL, MICROGRID, PHOTOVOLTAIC		1	LS		2,524,500	1,942,550
15 SECURITY 17 VOICE DATA OBECIAL SYSTEMS & TELECOMMUNIC	CATIONS	1			200,000	245 100
10 VOICE, DATA, SPECIAL STSTEMS & TELECOMMONY	CATIONS	1	Lo		370,200	345,100
Sublotal	Migroprid Alternate with Ower	and and	Drofit		16,023,866	12,010,505
With 10% 2022 Inflation	Microgrid Alternate with Overn	cau anu	FIOII			13 780 805
With 6% 2023 Inflation						14 607 654
With 3% 2024 Inflation						15 045 883
Design / Bid Contingency 10%					1,602,387	1,504,588
	Building Construction Co	sts Sul	bTotal		17,626,252	16,550,472
	Construction C	Continger	ncy 5%		881,313	827,524
	BUILDING CONST	RUCTI	ON CO	DST TOTAL	\$18,507,565	\$17,377,995

Soft Costs:					
40.40 Hazard Material survey, sample, test	0	LS	3,500.00	0	0
40.50 Hazardous material abatement	0	SF	4.00	0	0
40.60 Legal Fees	1	LS	10,000.00	10,000	10,000
40.70 Ownership and Deconstruction Insurance	1	LS	5,000.00	5,000	0
40.80 Phase 1 Environmental Study	1	LS	5,000.00	5,000	0
40.90 Phase 1 Archeological Study	1	LS	5,000.00	5,000	0
40.10 Final Equipment and Utility connections on site	1	LS	5,000.00	5,000	0
41.00 Professional Fees: Civil Engineering	1	LS	87,000.00	87,000	62,987
41.01 Professional Fees: Landscape Architecture	1	LS	17,000.00	17,000	25,195
41.02 Professional Fees: Programming	1	LS	30,000.00	30,000	30,000
41.03 Professional Fees: MEP Engineering	1	LS	370,000.00	370,000	314,935
41.04 Professional Fees: Data, security, access control audio	1	LS	20,000.00	20,000	29,520
41.05 Professional Fees: PV Design	1	LS	12,000.00	12,000	0
41.06 Professional Fees: Architecture/Interior Design	1	LS	720,030.00	720,030	730,655
41.07 Professional Fees: Structural Engineering	1	LS	143,970.00	143,970	125,974
41.30 Design Team Reimbursable Expenses	1	LS	18,000.00	18,000	18,000
41.40 Fundraising Feasibility Study	1	LS	0.00	0	0
41.50 Sustainability Design Fees	1	LS	50,000.00	50,000	50,000
41.60 Owner's rep/Construction Management Services (Design and Construction)	1	LS	400,000.00	400,000	719,850
41.60 Commissioning	1	LS	30,000.00	30,000	30,000
41.80 LEED certification fees from USGBC	1	LS	12,000.00	12,000	12,000
41.10 Furnishings Design, selection, bidding Fees,	1	LS	150,000.00	150,000	159,016
41.11 Geo Thermal Test Well	1	LS	12,000	12,000	12,000
41.12 Topographical Site Survey \$6k, CSM Certified Survey Map \$5k	1	LS	11,000.00	11,000	6,500
41.13 Geotechnical subsurface investigation;	1	LS	5,200.00	5,200	7,500
41.14 Quality Control Material Testing & Inspections	1	LS	30,000.00	30,000	30,000
42.00 Printing, shipping, & plan room Costs for Construction Documents	1	LS	11,000.00	11,000	11,000
43.00 State Construction documents review Fees	1	LS	10,000.00	10,000	0
44.00 City Plan Review Permits and Fees	1	LS	10,000.00	10,000	10,000
45.00 Builders Risk Insurance	1	LS	7,000.00	7,000	7,000
46.00 Construction Utility costs by Owner	1	LS	10,000.00	10,000	10,000
47.00 Fixtures, Furnishings, blinds, & Equip Allowance \$28/SF new	24,915	SF	28.00	697,620	711,200
47.00 Fixtures, Furnishings, blinds, & Equip Allowance \$14/SF Existing	36,143	SF	14.00	506,002	512,000
47.10 Appliances: fridge, coffee maker, ice maker, cooler	10	EA	750.00	7,500	0
48.00 Technology & Computer Equipment Allowance, (less use of existing)	22,085	SF	13.50	298,148	369,000
51.00 Moving costs for multiple phases of construction	1	LS	50,000.00	50,000	40,000
52.00 Ground breaking and dedication ceremonies	1	LS	3,000.00	3,000	3,000
53.00 Fundraising Consult anting & grant writing	1	LS	0.00	0	0
54.00 Soft Costs Contingency	1	LS	150,000.00	150,000	0
Soft Cost SubTotal				3,908,470	4,047,332
With 10% 2022 Inflation					4,452,065
With 6% 2023 Inflation					4.719.189
With 3% 2024 Inflation					4 860 765
and 570 EVE ( Innation	Building Construction Cost	Total		18 507 565	17 377 005
	bunding Construction Cost	rotai		10,307,303	11,311,393
PROJECT TOTAL COST				\$22,416,034	\$22,238,760

Updated Budget is based on the following UPDATED Schematic Design Drawings (Site and Architectural Plans and Elevations dated 8/29/2023) which includes:

Addition Size Reduction

- **Reduced Parking Lot Expansion**
- Reduced Sidewalk / Paving
- Cap of \$200,000 for Amphitheater Structure and Lighting
- Elimination of Second Drive Lane
- Reduction in Size of Atrium
- **Community Room Atrium Access**

Optional Alternates

- 1. Bird Safety Glazing 2. Geothermal Building System (System and Design Fees) if test well passes
- 3. Net Zero Building
- 4. Eliminate Atrium Beyond Reduced Size Shown

Previous, conceptual budget of \$19,988,281 excluded the following options:

Microgrid

Energy Efficiency Extents

Owner's Rep Services

Full building mechanical upgrades

These have been added to the project scope as part of the schematic design discussions.

#### ARCHITECTURE / ENGINEERING / INTERIORS

\$ 360,000.00 \$ 1,100,000.00 To Be Determined \$ (700,000.00)



# PROJECT TIMELINE

# SPPL PROJECT TIMELINE FEH DESIGN



		Poard montings socond Thursday of the month				
	_	Board meetings second Thursday of the month				
ACTIVITY	START	NOTES				
Client Project Kickoff Meeting Start	4/12/2023					
Program meeting	4/26/2023	9am				
Program meeting	5/8/2023	9am				
Schematic Design (3 months)	5/16/2023					
Core Planning Meeting	5/25/2023	12-2PM				
Finalize programming/space planning	6/8/2023	Library Board Meeting @ 6PM				
Core Planning Meeting	6/8/2023	12-2PM				
Core Planning Meeting	6/22/2023	12-2PM - Review Amphitheater Layout				
Core Planning Meeting	7/6/2023	12-2PM				
Core Planning Meeting	7/20/2023	12-2PM				
Staff Meeting	7/24/2023	1PM				
Staff Meeting	7/27/2023	9AM				
Core Planning Meeting	8/3/2023	12-2PM VIRTUAL				
Internal Quality Review	8/3/2023					
Schematic Design Complete	8/10/2023	Amphitheater and Maker's space layout for fundraising / Library Board Meeting @ 6PM				
Design Development Start	8/11/2023					
Core Planning Meeting	8/17/2023	12-2PM				
Core Planning Meeting	8/31/2023	12-2PM				
Special Library Board Meeting	8/31/2023	6PM				
Special Committee of the Whole Meeting	9/12/2023	5:30PM				
Core Planning Meeting	9/14/2023	12-2PM				
Core Planning Meeting	9/28/2023	12-2PM				
Core Planning Meeting	10/12/2023	12-2PM				
Core Planning Meeting	10/26/2023	12-2 PM				
Core Planning Meeting	11/2/2023	12-2PM VIRTUAL				
Internal Quality Review	11/2/2023					
Design Development Complete	11/9/2023	Library Board Meeting @ 6PM				
Contract Documents Start	11/9/2023	12-2PM				

ACTIVITY	START
Core Planning Meeting - As Needed	11/23/2023
Core Planning Meeting	12/7/2023
Core Planning Meeting	12/21/2023
Core Planning Meeting	1/4/2024
Core Planning Meeting	1/18/2024
Core Planning Meeting	1/25/2024
Internal Quality Review	1/25/2024
Contract Documents Complete	2/9/2024
Library Board Approval to Issue Drawings	2/8/2024
City Council Approval to Issue Drawings	2/21/2024
Issue drawings to Bid	2/23/2024
Receive Bids	3/19/2024
Recommendation to Award	4/12/2024
City Council Approval of Award	4/17/2024
Start Construction process (13 months)	4/30/2024
Groundbreaking Ceremony	June 2024
Ongoing Bi-Weekly Progress Meetings	
Substantial Completion	5/30/2025
Furniture Installation	6 weeks
Final Completion Date	7/18/2025
Technology Installation	4 weeks
Move	August 2025
Grand Opening and Dedication	September 20

	NOTES
	12-2PM
	12-2PM
l	12-2PM
	12-2PM
	12-2PM
	12-2PM VIRTUAL
	Library Board Meeting @ 6PM
	Library Board Meeting @ 6PM
	(If Needed)
5	
2025	



# **MEETING MINUTES**

MEE	TING INFORMATION			
MEE	TING NAME	SD Kickoff Meeting	MEETING LOCATION	Sun Prairie Library
MEE	TING DATE	25 May 2023	MEETING TIME	12:00pm-2:00pm
PRO	JECT NAME	Sun Prairie Library Remodel	and Addition	
FEH	PROJECT NUMBER	2023402		
PRO	JECT ADDRESS	1350 Linnerud Dr		
		Sun Prairie, WI 53590		
ATTE	ENDEE NAME	ORGANIZATION	PHONE	EMAIL
$\boxtimes$	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com
$\boxtimes$	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com
$\boxtimes$	Brady Ludvik	FEH Design		bradyl@fehdesign.com
	Anders Dahlgren	Library Planning Associates	309.846.2836	libraryplanningassoc@gmail.com
$\boxtimes$	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com
$\boxtimes$	Kevin Johnson	Hunzinger – Owner's Rep	262.432.9166	kevinjohnson@hunzinger.com
	Theresa Stevens	SPPL Foundation Exec Director	608.886.0718	execdirector@sunlibfoundation.org
	Jeff Robbins	Sun Prairie Media Center		jrobbins@cityofsunprairie.com
$\boxtimes$	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org
$\boxtimes$	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com
$\boxtimes$	Jan Holmes	Tech coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com
$\boxtimes$	Kate Hull	Tech services - SPPL	608.825.0901	khull@cityofsunprairie.com
$\boxtimes$	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com
$\boxtimes$	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com

#### DISCUSSION

- 1. Goals for Success
  - a. Kate read though the Goals, no changes were made.
  - b. Christy stated that the goals will be read at each meeting to guide the design process.
- 2. Timeline
  - a. June 8<sup>th</sup> is a library board meeting, there will be an action item to approve the program.
  - b. Planning meetings will be every other Thursday from 12:00 pm 2:00 pm.
  - c. The amphitheater design meeting will be 6/22/2023.
  - Schematic Design is to be complete on 8/10/2023. d.
  - e. The internal quality review meetings are internal and there will NOT be an owner meeting.
  - Design Development is to be completed 11/9/2023. f.
  - Contract Documents are to be completed 2/8/2024. g.
    - i. The documents will need to go to City Council for approval on Feb 20.



		ii.	The bid documents could be
3.	Program	<b>n</b> – Space	e Needs Summary
4.	Design	review	
	a.	The plar	n was reviewed.
	b.	Adult Se	ervices
		i.	It was requested to swap the
		ii.	Large Print should be near t
		iii.	The Library of Things has no
			1. This could be place
			removed.
		iv.	It was determined that there west.
		۷.	The group liked that the brea
			like the lack of windows or th
			walls.
			<ol> <li>Skylights would be</li> </ol>
		vi.	More seating is needed in th
			determined.
		vii.	The Renk room needs more
			together to create larger sur
		viii.	Book club kits could be hous
		ix.	Periodicals could be on low
	с.	Youth S	ervices
		i.	The mechanical room was n
			systems.
		ii.	There will be battery storage
			outside of the fence if possib
		iii.	If the mechanical room, as s
			the roof in a penthouse.
		iv.	The mechanical room will ne
		۷.	The teen staff person does r
		vi.	It was confirmed that 8 staff
		vii.	Transitional chapter books s
		viii.	Multifunction printing should
		ix.	Parenting books should be le
		х.	A care cabinet needs to be a

- xi. One 6-person study room and one 3-person study room are shown in Youth Services.
- xii. Small toilets for children should be provided in bathrooms in youth services.
- xiii. In Teen, non-fiction and graphic novels should be swapped.
- acoustics.
- The exterior door should be a standard double door.

SIOUX CITY / DES MOINES / DUBUQUE / OCONOMOWOC

issued a few days later.

- e fiction and nonfiction collections.
- he reference desk.
- ot been located on the plan yet.
- ed along the west side of the Teen area, where the wall opening was
- should not be an opening from Teen into the Adult collection to the
- ak room was more accessible to the Media Center staff but did not he restroom door locations. The break room will need acoustic-rated
- an option for natural light into the breakroom. ne Renk Room. The type of seating (lounge or upright) is to be
- tables for up to 15 people to meet. Tables could be pushed faces.
- sed in the Renk Room.
- shelving outside of the Renk Room.
- noved to the exterior of the building, as required for the building
- outside as part of the microgrid system. It was preferred to be ole.
- shown, is not sized sufficiently, equipment will need to be added to
- eed to be sound proofed.
- not need an office.
- need workspaces in the youth workroom.
- should be in grade school.
- be provided in youth services.
- ocated in the children's hub.
- added into the teen space. It is currently a wardrobe unit.
- xiv. The Teen area will have full-height walls that have partial height glass for supervision and

xv. Story Time should have an operable partition as the interior wall, to open the space for overflow.



#### d. Media Center / Maker Space

- i. It is important for staff to be able to view the maker spaces from the youth services space.
  - Since the current layout makes this difficult, FEH Design should develop additional options for the room layout, including mirroring the location of the studio spaces or separating them.
- ii. Glass on north and south maker space walls to allows passersby to see the activity going on.
- iii. Equipment in studio spaces still needs to be determined.
- iv. The intent is to have separate low-tech and high-tech areas in the makerspace.
- e. Staff
  - i. More natural light was requested for the staff area.
  - ii. The Circulation staff doesn't need lateral files at the workstations.
    - 1. 4 desks should be provided including 1 at the pickup window.
  - iii. The door to the existing mechanical room should remain for access.
  - iv. A door to Friends from the staff space should be provided.
  - v. 3 bins should be provided in the book drop.
  - vi. The dimensions of the existing sorter should be verified to show it properly on the plans.
  - vii. The location of the break room was discussed. Options of the staff area should be created to review at the next meeting.
- f. Friends / Café
  - i. Space is needed outside of the store to display books, something that will take up less space than the existing table. Options will be provided at the next meeting.
- g. Other
  - i. The atrium is full of hard surfaces, so acoustical materials may need to be suspended from the ceiling or other strategies.

#### 5. Other items

- a. Sustainability
- b. Funding Source Requirements

#### 6. Next steps and assignments

a. Focus on Energy Meeting Wednesday, May 31 at 10AM

#### **ACTION ITEMS**

#### 1. FEH Design

- a. Create options for the maker space and staff areas.
- b. Verify the existing sorter dimensions and configuration.
- c. Update plans based on comments.
- 2. SPPL
  - a. Provide comments to Svetha, who will send them to FEH Design prior to the next meeting.

For meeting minutes this is the author's understanding of the items discussed. Please notify us of any discrepancies within 7 days so revised minutes can be issued. No response will indicate acceptance by all parties.

WRITTEN BY	Christy Monk	
NEXT MEETING	June 8th, 2023, at 12PM	
ATTACHMENTS	Goals for Success, Floor Plans	



# **MEETING MINUTES**

MEE	TING INFORMATION					
MEE	TING NAME	SPPL SD Meeting	MEETING LOCATION	Sun Prairie Public Library and Zoom		
MEE	TING DATE	8 June 2023	8 June 2023 MEETING TIME			
PRC	JECT NAME	Sun Prairie Public Library Remodel and Addition				
FEH	PROJECT NUMBER	2023402				
PRC	JECT ADDRESS	1350 Linnerud Drive, Sun Pra	airie WI 53590			
АТТ	ENDEE NAME	ORGANIZATION	PHONE	EMAIL		
$\boxtimes$	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com		
$\boxtimes$	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com		
$\boxtimes$	Theresa Stevens	SPPL Fdn Exec Director	608.886.0718	execdirector@sunlibfoundation.org		
$\boxtimes$	Anders Dahlgren	Library Planning Associates	309.846.2836	libraryplanningassoc@gmail.com		
$\boxtimes$	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com		
$\boxtimes$	Brady Ludvik	FEH Design	262.968.2055	bradyl@fehdesign.com		
$\boxtimes$	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com		
$\boxtimes$	Kevin M. Johnson	Hunzinger – Owner's Rep	414.416.3377	kevinjohnson@hunzinger.com		
	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org		
$\boxtimes$	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com		
$\boxtimes$	Jan Holmes	Tech Coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com		
$\boxtimes$	Kate Hull	Tech Services - SPPL	608.825.0901	khull@cityofsunprairie.com		
$\boxtimes$	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com		
$\boxtimes$	Sandy Xiong	City of Sun Prairie	608.825.0893	sxiong@cityofsunprairie.com		
$\boxtimes$	Jeff Robbins	Sun Prairie Media Center		jrobbins@cityofsunprairie.com		
$\boxtimes$	Terry McIlroy	City of Sun Prairie	608.354.8513	District1b@cityofsunprairie.com		
$\boxtimes$	Steve Stocker	City of Sun Prairie Alderperson, Library Board Liaison	608.354.8511	sstocker@cityofsunprairie.com		

1. Introductions

#### 2. Goals for Success

a. The goals were read aloud, no changes were made.

#### **3. Program** – Space Needs Summary

- a. Anders discussed the workbook version 1.2.
- b. Seeking recommendation from the Library Board to move forward with developing the plan.
  - The program is a set of instructions on how to shape the plan. This document:
    - 1. should be developed by a librarian.
    - 2. identifies resources, services, and spaces in an increasing level of detail.



- - a. The bottom shelf is not used in the current iteration.
- ii. The plan should capture the essence of the program.

#### 4. Timeline Update

- b. The meeting shown the week of Thanksgiving will be as needed and may be online.

#### 5. Design Review

- a. Adult Services
  - i. The staff area has been rearranged per comments after the last meeting.
  - ii. The existing IT closet has been shown by reference station.
  - iii. Nonfiction and adult fiction have been swapped.
  - iv. Large print is near reference station.
  - v. Reference documents are near computers.
  - vi. DVDs and music is near the main aisle.
  - vii. The Renk room has been reorganized with nesting tables.
    - 1. Local history shelves and a museum display cabinet are shown in the space.
  - viii. Graphic novels should be moved to shelving between audio books and science fiction.

  - xi. The print release and copy center names should be swapped.
- b. Youth Services (Options)
  - i. The teen windows do not start until north of Library of Things. 1. Library of Things size and shelving quantity still needs to be determined.
  - ii.
  - iii. A hub of computers should be created between age groups.

  - v. The youth services offices and workroom options were reviewed.
    - 1. The second option (numbered 4 on the plan sheet A1.3) was preferred.
    - ready room, storage.

    - c. Each block of staff offices should have a ready room.

  - vii. Another reading "cubby" is to be added for a total of 2.
  - mounted manipulatives.
  - ix. The board book layout should be less rigid and more organic (think baby playland)
    - 1. Typically, there is a large portion of the collection checked out.

#### SIOUX CITY / DES MOINES / DUBUQUE / OCONOMOWOC



1241 CORPORATE CENTER DRIVE OCONOMOWOC, WISCONSIN 53066 262 968 2055

3. is a work in progress. A variance between what the program says and what the plan says is expected. The program overstates the library space needs to make sure there is truly enough space.

a. Add groundbreaking should be added for the end of May 2024 and a proposed ribbon cutting should be added.

2. Periodicals and newspapers are below the windows on the outside of the Renk room.

3. Reading club kits moved out of the Renk room since they took up a large amount of space.

ix. It was requested that a window be added from the staff area to the print release, potentially at the countertop.

x. A window wall should be added between Adult Services Office 1022 and Adult Staff 1023.

Picture books shelving should be 42" tall (it is tagged incorrectly but the quantity is accurate).

iv. The existing teen furniture will need to be inventoried for reuse into the design of the addition.

a. Supervisors need their own office, meaning they need 3 subsidiary rooms in this space - office,

b. The Youth Services director's office should be in the southeast corner.

i. The two full-time employees need larger desks and dual monitors.

vi. The aquarium was shifted to have a larger gathering space in the entry to the youth area.

viii. The mechanical room door should be moved closer to the offices. That wall may be used for a mural or wall-



- x. Early readers should be 42" high.
- c. Media Center / Maker Space (Options)
  - Storage should be provided near the Media Center welcome desk for equipment checkout.
  - The studio spaces in the makerspace were reviewed: ii.
    - 1. Currently shown are (2) 300 SF studios.
      - a. Video studio can be 250 SF.
      - b. Audio studio can also be 250 SF.
    - 2. There was discussion about changing to one studio; it was determined to stay with the current configuration of two for the time being.
    - 3. The equipment for the studios is not currently in the construction budget. The media center is working on raising funds for equipment.
    - 4. The option with the studios in the northwest corner of the makerspace was preferred. If the space is reconfigured, the overall space will not be reduced.
    - 5. The Library of Things shelving quantity and type will need to be determined; these may need doors.
- d. Staff (Options)
  - There was a preference for the option with an exterior window in the break room. i.
  - ii. It was recommended to swap Ready Room 1079 and Maintenance Office 1014.
  - iii. Automated book drops can slow things down at the drive-up book drop, so there is a preference for carts currently. Space should be provided for a small sorter in the book drop in the future.
  - iv. There is a preference to provide a configuration so the administrative workstation is not a walkthrough space and feels more private.
  - v. There was a preference for the layout shown in the main floor plan with minimal edits, no options.
  - vi. Bench space is needed for technology (maybe in the maintenance office or garage). This can also be movable or temporary.
- e. Friends / Café
  - The shelving in front of Read Before Book Store has been revised to be 2 shelves high with spine-out and i. face-out orientation.
  - ii. This area will have a machine to dispense coffee drinks and prepackaged food items.

#### 6. Other items

- a. Sustainability
  - FEH Design is working with the engineering team on information related to the microgrid grant. i.
  - The initial Focus on Energy (FOE) meeting was last week. The next meeting will be at the end of July. ii.
    - 1. Their engineer is working on different options/bundles.
      - a. Baseline all electric with photovoltaic and microgrid.
      - b. Ask FOE to send the bundle options a minimum of 1 week before the meeting for everyone to review.
    - 2. FOE requested the anticipated hours of operation.
      - a. The existing library hours will be used.
      - b. The lobby space will have one extra hour at the beginning and end of each day.
    - 3. WPPI and SPU to be added to the FOE meeting group.
  - iii. A sustainability coordinator for the City is anticipated to start in August.
- b. Funding Source Requirements
  - Let FEH Design know of any new grants and what requirements they would be adding.



#### 7. Next steps and assignments

- a. Library Board Meeting Tonight!
- b. Next Chapter Team Meeting June 22 @ 12PM
- c. Refine and look beyond floor plan
  - i. Amphitheater layout to be discussed start meeting with this.

  - next meeting to be part of the amphitheater discussion.
- schematic design. The motion was unanimous and will be presented to the Library Board.

#### **ACTION ITEMS**

#### 1. FEH Design

- a. Update plans with comments
  - b. Invite Synder and Associates to next meeting.
- 2. SPPL

For meeting minutes this is the author's understanding of the items discussed. Please notify us of any discrepancies within 7 days so revised minutes can be issued. No response will indicate acceptance by all parties.

WRITTEN BY	Brady L / Christy Monk
NEXT MEETING	June 22, 2023, at 12PM
ATTACHMENTS	Goals for Success, Timeline, Floor Plans

1241 CORPORATE CENTER DRIVE OCONOMOWOC, WISCONSIN 53066 262 968 2055

ii. Snyder & Associates will be providing the Civil Engineering and Landscape Architecture. They will be at the

d. The Next Chapter Team endorses the program and recommends continued development of the plan into

a. Staff should provide comments to Svetha and she will send them to FEH Design.



# **MEETING MINUTES**

ME	TING INFORMATION			
ME	TING NAME	SPPL SD Meeting	MEETING LOCATION	Sun Prairie Public Library Community Room and Zoom
ME	TING DATE	22 June 2023	MEETING TIME	12:00PM
PRC	JECT NAME	Sun Prairie Public Library Re	model and Addition	
FEH	PROJECT NUMBER	2023402		
PRC	JECT ADDRESS	1350 Linnerud Drive, Sun Pra	airie WI 53590	
ΑΤΤ	ENDEE NAME	ORGANIZATION	PHONE	EMAIL
$\boxtimes$	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com
$\boxtimes$	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com
$\boxtimes$	Theresa Stevens	SPPL Fdn Exec Director	608.886.0718	execdirector@sunlibfoundation.org
$\boxtimes$	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com
$\boxtimes$	Brady Ludvik	FEH Design	262.968.2055	bradyl@fehdesign.com
$\boxtimes$	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com
$\boxtimes$	Scott Anderson	Snyder & Associates, Inc.	608.838.0444	sanderson@snyder-associates.com
$\boxtimes$	Andy Meessmann	Snyder & Associates, Inc.	608.838.0444	ameessmann@snyder-associates.com
$\boxtimes$	Kevin M. Johnson	Hunzinger – Owner's Rep	414.416.3377	kevinjohnson@hunzinger.com
$\boxtimes$	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org
$\boxtimes$	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com
$\boxtimes$	Jan Holmes	Tech Coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com
$\boxtimes$	Kate Hull	Tech Services - SPPL	608.825.0901	khull@cityofsunprairie.com
$\boxtimes$	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com
	Steve Stocker	City of Sun Prairie Alderperson, Library Board Liaison	608.354.8511	sstocker@cityofsunprairie.com
$\boxtimes$	Jeff Robbins	Sun Prairie Media Center		jrobbins@cityofsunprairie.com
the second se				

#### 1. Goals for Success

A. The goals were reviewed.

#### 2. Amphitheater

- A. Inspiration Images
  - Snyder & Associates presented some inspiration images (attached) for the group to provide input on what they liked and what they didn't for the amphitheater.
  - The current layout is based off the initial design rendering. ii.
    - a. There are 5 levels and the height between tiers is 18-inches. Each tier has a 12-inch-deep stone edge that can be used for a seat.
    - b. There will be a band shell on the 'stage' level.
  - The group stated the strong need to have shade for the outside spaces, to be usable iii. during the morning and afternoon in the summer.
    - a. Large children's programs will use the amphitheater. No sit-down programs will use the children's patio.
    - b. The amphitheater is south facing, which will make it sunny and hot.



- years for the trees to mature.

#### B. Landscaping

- - amphitheater.
  - as athletic turf with rubber pellets.

#### C. Layout

- handicap seating at the end of each tier.
- ii. performers can get equipment down to the stage.
- iii. There is already a donor for the stage. iv. the donors will be engraved on the stone seats.
- crosswalk to help with pedestrian traffic.

#### 3. Site Plan Review

- - ii. iii.
- ٧.
  - table here to slow down traffic.
- There will be dedicated bike parking. vi.
- - paths.
- native plants that can withstand the water. E. Site Amenities
- i. Bike racks
  - ii. 2 locations for vehicle charging – 4 spots total

c. The design team will work to create shading options for the amphitheater. d. There was discussion about adding shade structures. There was concern about the size of the foundations for the poles. The poles and shades could block views in the amphitheater too. Adding large evergreens south / southwest of the band shell would create shade and buffer sound. e. It was ultimately decided to add trees south of the band shell to create shade. Smaller trees are to be added to the tiers to create shade. It will take a few

i. It was determined that there should be softscape on the tiers. There was discussion on whether it should be natural grass or synthetic turf.

> a. Turf would reduce the long-term maintenance but would still need some occasional cleaning. Food and drink should be limited on the turf. b. There is currently no irrigation planned for the project. A hose bib is

recommended to be on the southeast side of the building for use at the

c. Kevin mentioned the company Forever Lawn. This type of turf is not the same

It was initially decided to make all levels accessible. There will need to be an area for

An 8' wide path will be added to the band shell from the parking lot so bands/

The seats are just starting to be sold. There are to be 200 donor seats. The names of

a. The stone edge may have to increase to 18" deep.

v. A sidewalk from the street to the amphitheater is to be added. There was discussion on where this should be located if people are coming from the park to the library.

There was a recommendation that the city should plan in the future to create a

A. Snyder and Associates presented the overall site layout (see attached).

Parking will be added to the northeast and will follow the property line.

The new entrance lane will have a 'traffic calming' curve.

It was discussed to make the existing drive one-way. The book drop will remain on the west side of the building; it would be a long drive though the whole parking lot to enter or exit. It was determined that the corner of the existing drive into the parking lot will be reworked and the drive will remain two-way.

iv. Accessible parking will be at both entrances (new and existing).

An off-loading zone has been added at the new / east entrance. There will be a speed

B. It was asked where the geothermal will be located. It will be under the east parking lot.

C. Prairie areas were discussed. Since the building will be located on the existing prairie, Synder is showing an area southwest of the amphitheater that will replace what has been developed. i. It was suggested to extend the existing sculpture path to connect to amphitheater

D. Stormwater drainage will run along the north to the east detention basin. The basin will have



- a. Check with the utility on rapid chargers and what type of chargers can be provided.
- F. Parking lot islands are intended to be filled with low height prairie grass and trees.
  - i. Make sure the long grass is not too tall, to avoid visibility issues.
  - ii. The city has a forestry individual who may get involved in the project.
- G. Synder will look at the staff building entrance on the west side of the building and make suggestions regarding how that can be improved for the safety of staff with the book drop traffic.

#### 4. Design Review

- A. Café Space
  - There is to be a door between the bookstore / café and back-of-house. i
  - ii. 2 to 3 café tables should be provided.
  - iii. An awning or element should be added to make the space feel like a café.
- B. Library of Things (LoT)
  - i. The LoT will remain by teens for now. It was requested that area also have teen books for non-teen patrons.
    - a. This can be standard shelving for now, as it still needs to be determined what type of items will be part of the LoT.
    - b. A seed library was mentioned.

C. Staff Space

- i. It is ideal to have the red bins by the sorter.
- Adding more natural light to the spaces should be considered via skylights or light ii. tubes.
- It was requested to have the desks in youth services face the door. iii.
- iv. The self-check and print release in the Adult space should be swapped and the selfcheck near reference should be removed.
- The Adult Services reference station should be moved south of the computers and the ν. rows of computers should be shifted north.
  - a. The desks in the Adult Services office will need to be rearranged for sight lines.
  - b. The door into Adult Services should be moved to the east wall and the door alcove removed.
- vi. The drive-up window will protrude out from the exterior wall, since the book drop wall is further west.
- D. Unsupervised space / surveillance
  - i. Surveillance camera locations will be reviewed at a future meeting.
    - a. An entirely new camera system should be provided.
    - b. The storage capacity will need to be determined currently have 12 days' worth before rewriting.
- E. Makerspace
  - Jeff stated he got a commitment from the Friends group to purchase equipment in the i. Makerspace studios.
  - ii. The layout should be retained with two studios.
  - iii. Plenty of outlets will need to be provided in the Maker Space.
- F. Furniture
  - Examples of furniture for the Library of Things, Periodicals, and Renk Room were i. briefly discussed. (see attached images)
  - ii. Options for the Read Before Book Store and face-out shelving were briefly reviewed. Low face-out shelving could be provided outside of the bookstore for after-hours browsing and sales.



#### 5. Other items

- A. Sustainability and Focus on Energy

  - Focus on Energy.
- B. Funding Source Requirements
- C. Community Room Rendering

#### 6. Next steps and assignments

- A. Next Chapter Team Meeting July 6 @ 12PM

#### **ACTION ITEMS**

#### A. FEH Design

- Update plans and provide exterior elevations
- B. Snyder
  - Update site plan ii.
- C. SPPL
  - iii. Provide preferred browser bin info to verify unit quantities.

For meeting minutes, this is the author's understanding of the items discussed. Please notify us of any discrepancies within 7 days so revised minutes can be issued. No response will indicate acceptance by all parties.

WRITTEN BY	Brady L / Christy Monk		
NEXT MEETING	July 6, 2023, at 12PM		
ATTACHMENTS	Goals for Success, Amph		

i. FEH Design will have the exterior elevations done by the end of month to send to

i. This meeting will be sometime in August. FEH Design will send information to Svetha.

B. Meetings with staff to be on July 24<sup>th</sup> afternoon (1:00pm) and 27<sup>th</sup> morning (9:00am).

itheater Inspiration Images, Site Plan, Floor Plans, Furniture Image



# **MEETING MINUTES**

MEE	TING INFORMATION			
MEE	TING NAME	SPPL SD Meeting	MEETING LOCATION	Sun Prairie Public Library Community Room and Zoom
MEETING DATE		06 July 2023	MEETING TIME	12:00PM
PRC	JECT NAME	Sun Prairie Public Library Re	model and Addition	
FEH	PROJECT NUMBER	2023402		
PRC	JECT ADDRESS	1350 Linnerud Drive, Sun Pra	airie WI 53590	
ΑΤΤ	ENDEE NAME	ORGANIZATION	PHONE	EMAIL
$\boxtimes$	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com
$\boxtimes$	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com
	Theresa Stevens	SPPL Fdn Exec Director	608.886.0718	execdirector@sunlibfoundation.org
$\boxtimes$	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com
$\boxtimes$	Brady Ludvik	FEH Design	262.968.2055	bradyl@fehdesign.com
$\boxtimes$	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com
$\boxtimes$	Kevin M. Johnson	Hunzinger – Owner's Rep	414.416.3377	kevinjohnson@hunzinger.com
$\boxtimes$	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org
$\boxtimes$	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com
$\boxtimes$	Jan Holmes	Tech Coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com
$\boxtimes$	Kate Hull	Tech Services - SPPL	608.825.0901	khull@cityofsunprairie.com
	Steve Stocker	City of Sun Prairie Alderperson, Library Board Liaison	608.354.8511	sstocker@cityofsunprairie.com
$\boxtimes$	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com

#### 1. Goals for Success

- 2. Amphitheater
  - A. It was asked if the existing sculpture by the road is moving to the front of the building. The site plan shows adding sidewalk where the sculpture is currently located. The intent is that the existing sculpture will get relocated to the front of the building and that will leave a spot for a new sculpture.
  - B. Layout
    - The group agrees with the tree shading locations and overall layout. i.
    - ii. The current design does not show every level accessible, that is difficult to do with the grades and with turf.
  - C. Stage Accommodations
    - Recently there was a program with 30 people, they could not all fit on the stage in the i. community room.
    - The current stage in the community room is 8' x 18' and that is not large enough for ii. active performers, such as acrobats and dancers.
    - iii. The acrobats would require a minimum stage size of 12-feet by 15-feet with a height of 15-feet. Larger would be better.
    - The band shell at Whitmore is 28'x28' and is too small for the community band. iv. a. The community band would be the largest group to use the stage.



	۷.	Overflow strategy
		a. The first row of s
		many performers
		b. Depending on the
	vi	There was a conversation
	vi.	accommodate
		accommodate.
		b It was suggested
		b. It was suggested
		not be too large
		C. There was a fem
	D. Tun	This material may not we
	ι.	is chosen
		is chosen.
		a. It should be mad
		b. It can get warme
		lt must most LEE
		d It has soome as
		Other entions then grees
		Other options than grass
		e. Crushed pink gra
		I. Clover
		g. Softer rubberized
		n. Kevin brought up
		2. Bayshore
	Ш.	It was questioned what ty
		a. Soft and not not
	III.	The long-term cost comp
		a. FEH to look into
_		b. FEH to get samp
3.	Site Plan Revi	ew
	A. Overall	Layout
	i.	It was suggested that the
		existing parking lot. I wo
	ii.	It was asked how far awa
	<b>.</b>	is approximately 180 feet
4.	Design Reviev	
	A. Overall	Building Layout
	i.	The door on south side o

- B. Dishwasher / ADA Staff Spaces
- C. Building Elevations
  - and reused.
  - ii.
  - iii. windows are preferred.

1241 CORPORATE CENTER DRIVE OCONOMOWOC, WISCONSIN 53066 262 968 2055

eating can be used as overflow stage space if there are too

e type of performance, there could be seats for performers shell.

n about what size group the band shell should be designed to

in currently fit on the stage.

to ask members of the community band, or other groups g the space, to consider a donation if they would like to performing space. There is concern that the stage should that it would dwarf the smaller, more typical performances. inder that \$250,000 has been pledged for the stage.

ork well with sustainability goals, depending on which product

le from recycled materials. than grass. There is an optional cooling layer to help with

ED criteria.

if a patch needs to be replaced it can be done without tearing of turf.

and turf mentioned:

anite

flooring

two sites in Milwaukee

Square is natural grass.

e Town Center is turf.

pes of grass should be used.

grasses

parisons were questioned between turf and grass.

this.

es.

drive lane have a wider opening to the street and the -way traffic will be retained on the west drive lane. ay the new parking lot will be to the community garden, which

f building to access patio will be primarily exit doors. These should be locked and have access control.

i. All countertops should be ADA accessible heights in staff spaces.

i. The new entrance shall look like original entrance, but it will be moved forward to accommodate new Atrium space. Pieces of the existing entrance may be salvaged

The existing skylights shall be replaced and some will be added in the addition. FEH Design will check LEED to see if we need operable windows; non-operable



- iv. It was suggested to locate some of the solar panels in visible areas on the exterior, such as the south sloped roof.
- v. FEH Design will check with structural to determine if ballast roofs can be removed or if the ballast will need to remain at the existing structure.
- vi. Atrium elevation
  - a. Would most likely be aluminum storefront, not curtain wall.
  - b. Kawneer 451T or thermally broken 6" storefront to be used.
  - c. The wall below the storefront will be stone.

#### 5. Other items

- A. Climate Champions program
  - i. The group is interested in pursuing this opportunity in April of 2024 since the project is out of the design phase.
- B. Sustainability and Focus on Energy
  - i. A July meeting has not yet been scheduled.
- C. Funding Source Requirements
- D. Community Room Rendering
  - i. The information about the rendering and timeline should be provided by FEH Design to Svetha.
- E. Collections
  - i. It was suggested that the bin sizes for neighborhoods be verified. There is concern that not enough space has been designated for 3,420 books.
- F. Improving infrastructure for comfort
  - i. It was questioned whether there are plans to manage humidity instead of just temperature with the AC system.
    - a. FEH and Mechanical team shall consider different mechanical options.
      - Newer mechanical units are more sophisticated to handle both temperature and humidity.
    - b. It is recommended that once the new system is installed, to work with a separate company to maintain the system. Trane currently does scheduled maintenance.
- G. It was suggested that the coiling door / shutter into the atrium from the community room be considered a project alternate, for cost purposes.
- H. The storage room doors in the community room should provide larger than a 6'-0" wide opening (could go up to 8'-0").

#### 6. Next steps and assignments

A. Next Chapter Team Meeting July 20 @ 12PM

#### **ACTION ITEMS**

#### A. FEH Design

- i. Update design drawings
- ii. Get information on amphitheater surfacing (turf, etc)
- iii. Verify collection count capacity in neighborhood bins.

For meeting minutes, this is the author's understanding of the items discussed. Please notify us of any discrepancies within 7 days so revised minutes can be issued. No response will indicate acceptance by all parties.

WRITTEN BY	Brady L / Christy Monk
NEXT MEETING	July 20, 2023, at 12PM
ATTACHMENTS	Goals for Success, Site Plan, Floor Plans, Exterior Elevations



# **MEETING MINUTES**

MEE	TING INFORMATION			
MEETING NAME		SPPL SD Meeting	MEETING LOCATION	Sun Prairie Public Library Community Room and Zoom
MEETING DATE		20 July 2023	MEETING TIME	12:00PM
PRO	JECT NAME	Sun Prairie Public Library Re	model and Addition	
FEH	PROJECT NUMBER	2023402		
PRO	JECT ADDRESS	1350 Linnerud Drive, Sun Pra	airie WI 53590	
ATTENDEE NAME ORGANIZATION PHONE EMAIL			EMAIL	
$\boxtimes$	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com
$\boxtimes$	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com
	Theresa Stevens	SPPL Fdn Exec Director	608.886.0718	execdirector@sunlibfoundation.org
$\boxtimes$	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com
$\boxtimes$	Brady Ludvik	FEH Design	262.968.2055	bradyl@fehdesign.com
$\boxtimes$	Sarah Jansen	FEH Design	262.968.2055	sarahjj@fehdesign.com
$\boxtimes$	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com
$\boxtimes$	Kevin M. Johnson	Hunzinger – Owner's Rep	414.416.3377	kevinjohnson@hunzinger.com
$\boxtimes$	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org
$\boxtimes$	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com
$\boxtimes$	Jan Holmes	Tech Coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com
$\boxtimes$	Kate Hull	Tech Services - SPPL	608.825.0901	khull@cityofsunprairie.com
$\boxtimes$	Steve Stocker	City of Sun Prairie Alderperson, Library Board Liaison	608.354.8511	sstocker@cityofsunprairie.com
$\boxtimes$	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com

#### 1. Goals for Success

A. The Goals were read.

#### 2. Timeline

- A. A Next Chapter virtual team meeting will be scheduled for August 3.
- B. If possible, the Library would like to have summer programming onsite in 2025.
- Existing spaces will be minimally impacted in the summer of 2024, so summer programs could C. likely happen inside while the addition is being built.

#### 3. Cost Considerations

- A. After conducting the code review, it was determined that a fire separation wall is necessary between new and existing portions of the building.
- i. FEH Design is trying to maintain as much of the existing east exterior wall as possible. B. Sustainability priorities
  - The original opinion of probable cost continued using the natural gas fuel system and i i replacing the existing rooftop mechanical units.
    - a. The existing ductwork infrastructure will be reused, which reduces waste in the landfill.
    - b. LEED Gold can still be achieved with this revised strategy.



	ii.	Gec the fully	c. d. othe enti v ele a. b. c.	There will be one Doing a one-for-or- rmal will be utilize re building so futu- ectric geothermal. The city council w provide a comple Based on funding additional funding There was discus Construction cos reimburse.
Design	Review	v		
A.	Code F	Plan		
	i.	The	flo	or plan and assoc
В.	Site Pla	an		
	i.	The	do	or to the patio mov
		pro	grar	nming.
	11.	The	ou	tdoor patio to the
C	Ruildin	SIZE n Dou	e. moli	ition Plan
0.	i	The		rrent Storvtime roo
		bau	ates	5.
D.	Overal	Build	ding	Plan
	i.	The	bin	is count was incre
	ii.	Hub	) ma	aterials were split,
		from	n th	e desk into teen.
		Ine	DO Din	okstore point of sa
		mat	а	FEH will rearrand
			u.	south wall.
	iv.	The	sei	nsory room walls r
	ν.	Cos	st sa	wing methods we
			a.	One suggestion
				<ul> <li>The was</li> </ul>
			h	tor the st
			υ.	story time room
				shuffling of eleme
			c.	Reducing atrium
				conference room
				Th: 1.4

- - black metal.
- - 0

4.

1241 CORPORATE CENTER DRIVE OCONOMOWOC, WISCONSIN 53066 262 968 2055

control system for the building systems.

one rooftop unit replacement could reduce renovation time. ed for the addition. The geothermal well field will be sized for are phases could update the existing building equipment to

will be disappointed that the budget does not currently etely electric building.

g limits, it is unlikely the city would be able to provide g to convert the building to a fully electric geothermal system. ssion about grants, but they only cover a portion of the cost. sts would need to be paid up front and the grant would likely

iated occupant load was reviewed.

ved to the east side of Teen. This works better for

west was narrowed and the patio to the south was reduced in

om needs to be updated in the floor plan to show the recent

eased for the neighborhood collection – 14 bins. giving more visibility to the youth desk and better sight lines

ale was moved to north side of room and placed the coffee ecause there is existing plumbing in that wall.

ge furniture in this area but keep the coffee machine on the

need acoustic separation.

re reviewed.

was to reduce the building width in Youth Services.

her and dryer will move to the Janitor room and that will allow torage room to reduce in size.

d whether the discovery zone could be located within the when there is no programming. This would cause constant ents and was not feasible.

space so the vestibule would shift to the west, just east of the off of the atrium.

• This would eliminate stroller parking in the atrium.

d. The patio east of the storytime room can be reduced. The path needs to be wide enough for 2 strollers (approximately 8-feet wide).

• The fence needs to remain for safety.

• A masonry pier entry should be created but the fence could be basic

• This would have a storywalk along the fence.

e. The garage will be converted into a carport with a wood slat or trellis wall to allow air flow and look pleasing.

• This will save cost because it will not be a conditioned space.

• This may need a lockable gate or locked equipment storage room. This space could be enclosed in the future.



- E. Roof Plan
  - The public wants to retain the look of existing building in the renovated areas. i.
    - a. It was determined to eliminate the mansard roof on the addition. The existing mansard roof is aesthetic and provides a screen for the mechanical equipment on the roof.
      - o A low slope roof with parapets will have a more modern look. It will also make the solar panels more visible.
      - FEH Design will update the design to produce an image of this.
    - b. It was determined to not continue the interior east/west gabled roof from the existing to the new.
      - The ceiling can still accentuate the axis of the building.
      - Skylights could still be provided in this area with a low-slope roof.
      - FEH Design will update the design to produce an image of this.
- F. Building Elevations will be updated.
- G. Building Sections show the massing of the building.
- H. Building Reflected Ceiling Plan
  - The intent of the design is to maintain exiting ceiling grid where possible and update i. acoustical ceiling tiles (ACT).
  - The whole building will be getting new LED lighting. ii.
- Interior Camera Views 1.
- Furniture Plan J.
  - A "new materials" section in children's and teen collection should be provided. i.
  - It was requested that the full time YS staff desks be rotated to face the door. ii.
  - iii. The furniture plans should be updated for the staff meeting on 7/24.

#### 5. Other items

- A. Finishes Initial Thoughts
  - The intent is to update most finishes (wood trim and doors will remain). Brightening i. the space while keeping the original design is important.
  - The addition will have a more modern feel but have reflections of the existing building ii. in the new.
  - The wall colors should be a background for art. This includes framed art, murals and iii. picture rails.
  - Mission style furniture will not be continued in youth areas. iv.
    - a. Teen furniture is to be reused.
  - The group would like to keep the Renk Room feel the same and keep the stenciling. ν.
    - a. The genealogy group meets in the Renk Room and they need flexibility for seating. The traditional feel can be maintained.
    - b. The existing gas fireplace will be retained.
  - The group was reminded that LEED product pricing generally runs higher than the vi. 'traditional' products.
  - vii. FEH Design is to have finish samples at DD meeting on 8/17.
- B. Field Trips (Outdoor Spaces and Makerspaces)
  - Mitchell Street in Milwaukee i
  - ii. Need an outdoor space option to look at to look at turf.
    - a. Need to look at different turf options. It was requested to ask Forever Lawn for Dane County projects to look at.
  - UW Madison Memorial Union 3 different types of maker space elements. iii.
  - Watertown has maker spaces and the same material sorter. iv.
  - Menomonee Falls has a maker space. ٧.
  - vi. Waunakee
  - vii. Pinney Library
- Sustainability and Focus on Energy FEH Design will reach out and schedule a follow up C. meeting.
- D. 9/1 meeting to include IT systems.



#### 6. Next steps and assignments

#### **ACTION ITEMS**

#### 1. Assignments

- A. FEH Design:
  - i.
  - ii. Prepare SD booklet.
- iii. Start ordering finish samples.
  - Set up FoE meeting. iv.
- B. Next Chapter Team:
  - i. Field Trips

within 7 days so revised minutes can be issued. No i		
WRITTEN BY	Kim Bellmann/ Christy Mo	
NEXT MEETING	August 3, 2024 at 12:00PM	
ATTACHMENTS	SD Drawings	

#### A. Next Chapter Team Meeting August 3 @ 12PM - VIRTUAL to review SD Packet B. Committee of the Whole Presentation August 15 @ 5:30PM

Update plans based on changes made today.

For meeting minutes this is the author's understanding of the items discussed. Please notify us of any discrepancies sponse will indicate acceptance by all parties. nk



# **MEETING MINUTES**

MEE	TING INFORMATION										
MEE	TING NAME	SPPL SD Meeting	MEETING LOCATION	Zoom							
MEE	TING DATE	3 August 2023	MEETING TIME	12:00PM							
PROJECT NAME		Sun Prairie Public Library Remodel and Addition									
FEH PROJECT NUMBER		2023402									
PROJECT ADDRESS		1350 Linnerud Drive, Sun Prairie WI 53590									
ATT	ENDEE NAME	ORGANIZATION	PHONE	EMAIL							
	Svetha Hetzler	SPPL Director	608.825.0900	shetzler@cityofsunprairie.com							
	Rex Owens	SPPL Board President	608.513.1551	rexowens00@gmail.com							
	Theresa Stevens	SPPL Fdn Exec Director	608.886.0718	execdirector@sunlibfoundation.org							
	Kim Bellmann	FEH Design	563.583.4900	kimb@fehdesign.com							
$\boxtimes$	Brady Ludvik	FEH Design	262.968.2055	bradyl@fehdesign.com							
$\boxtimes$	Sarah Jansen	FEH Design	262.968.2055	sarahjj@fehdesign.com							
	Christy Monk	FEH Design	563.583.4900	christym@fehdesign.com							
	Kevin M. Johnson	Hunzinger – Owner's Rep	414.416.3377	kevinjohnson@hunzinger.com							
$\boxtimes$	Steev Baker	SPPL	262.365.4614	sbaker@sunlib.org							
	Lynn Montague	Youth Services - SPPL	608.825.0903	Imontague@cityofsunprairie.com							
$\boxtimes$	Jan Holmes	Tech Coordinator - SPPL	608.837.7323x2032	jholmes@cityofsunprairie.com							
	Kate Hull	Tech Services - SPPL	608.825.0901	khull@cityofsunprairie.com							
	Steve Stocker	City of Sun Prairie Alderperson, Library Board Liaison	608.354.8511	sstocker@cityofsunprairie.com							
	Erin Williams Hart	SPPL	608.825.0902	ewilliamshart@cityofsunprairie.com							
	Jeff Robbins	Sun Prairie Media Center	608.837.4193	jrobbins@cityofsunprairie.com							

#### 1) Goals for Success

- i) The goals were reviewed
- ii) Questions from August 1 COW Meeting
  - (1) The 20-year goal is an estimation for service to the anticipated, expanded population. It is not a statement about the building only being useful for 20 years. The building may not serve the population as well after 20 years.
  - (2) The goals are community-driven and refined over the last 5 years.
  - (3) Some goals are high level and are similar to other public libraries. The uniqueness is taking the goals and incorporating them into the design.

#### 2) Core Planning Team Meeting Schedule

- a) Keep Thursday noon meetings for now.
- 3) Design Review
  - a) 15 copies of the Schematic Design book are needed for the library board meeting.
  - b) The book includes the first 7 pages of Anders' Space Needs Summary.
  - c) FEH Design is to email a draft of the book to the team, for comment.
  - d) Narratives
    - i) Engineering
      - (1) The existing building has comfort and humidity issues. Doing a 1-for-1 rooftop unit replacement would not solve these issues.

SIOUX CITY / DES MOINES / DUBUQUE / OCONOMOWOC



- proposed.
- geothermal in the future.
- (4) Geothermal system is planned to be an add alternate. (a) The test well should still be performed to determine if the system is feasible.
- elements.
- (7) FEH Design will determine if the new mechanical room can be reduced.
- (8) All new restrooms will be gender neutral.
- e) Code Plan
- f) Site Plan
  - i) The path from the street to the amphitheater provides access to the park.
  - The path from the new parking to the east entrance will need to be more direct.
  - iii) The storm water will be kept on site and not tie into the city storm sewer immediately.
- g) Building Demolition Plan
- h) Overall Building Plan
  - from the exterior.
  - (a) The new restroom should be accessible from the interior.
  - ii) New exit from teen area on south side of building was added.
  - iii) The staff area was reworked based on comments
    - (1) Corridor to be made wider to accommodate red cart deliveries.
  - (2) Staff is to let FEH Design know how many carts they plan to have.
  - (3) Switching the library director's and the foundation director's offices was discussed. Svetha will talk to Theresa since she was not at the meeting.
  - iv) Read Before Book Store
  - v) Access control, particularly at exterior door locations, will be discussed at a future meeting.
  - vi) It was suggested to add a second computer / work station at the reference desk.
  - the youth services side can go to the floor.
- i) Roof Plan
- Building Elevations j)
- k) Building Sections
- Building Reflected Ceiling Plan
- m) Interior Camera Views
- n) Furniture Plan

#### 4) Opinion of Probable Cost

- a) Opinion of probable cost for the whole project is currently \$23,336,537.
  - i) Building construction cost is \$19,299,267.
  - includes all funding sources.
  - need-to-have items.
  - iv) Council could expect cost to be higher than predicted due to inflation
    - to be between 10 to 15 percent.

(2) 2 mechanical penthouses that will house 3 large air handling units tied to a central plant is being

(3) All proposed, new ductwork and controls will function the same when the system is switched to

- (5) The building will meet LEED Gold with the proposed mechanical system.
- (6) There will be a single direct digital control system. This will work with the microgrid and other electrical

i) A vestibule was added to the south side of building from the patio, which also provides access to a bathroom

(1) FEH Design should verify that the bookstore has as much or more shelf space than it currently has.

vii) Windows looking into teen space on the curved wall are to be higher, clearstory windows. The windows on

ii) The total project budget from conceptual design is \$19.988,281. This includes \$1,259,737 for design. This

iii) The team will need to be prepared to make cuts. Each department will need to make a list of nice-to-have vs.

(1) Steve Stocker asked City Engineering what percentage budget increases they are seeing in the current bidding climate, so the project will not exceed Council's expectations. The current increase was reported



#### 5) Other items

- a) Makerspace technology station(s) for digitization projects
  - i) The media center can do digitizing and they charge for it.
  - ii) Digitizing can be done in the maker space; the equipment is portable.
- b) SPMC Entry and Deliveries
  - i) The entrance will have key card access control from the atrium.
  - ii) During open hours, packages can get delivered through the atrium.
  - iii) After hours they will be delivered to receiving at the library.
    - (1) Signage could be added for delivery people drop their packages off in the atrium
  - iv) Media center staff will pick up their mail in the mail room that is part of the library.
- c) Sustainability and Focus on Energy

#### 6) Next steps and assignments

- a) Library Board Meeting August 10 @ 6:00PM
- b) Committee of the Whole Presentation August 15 @ 5:30PM
  - i) There is a template that will need to be used for the presentation.

#### **ACTION ITEMS**

- 1. FEH Design
  - a. Update plans based on changes
  - b. Finalize and print SD booklet
  - c. Begin ordering finish samples
  - d. Schedule FoE results meeting
- 2. SPPL
  - a. Library Staff to have their comments back to FEH by Tuesday 8/8/2023 at noon.
  - b. Field Trips to libraries and makerspaces

For meeting minutes this is the author's understanding of the items discussed. Please notify us of any discrepancies within 7 days so revised minutes can be issued. No response will indicate acceptance by all parties.

WRITTEN BY	Christy Monk					
NEXT MEETING	17 August 2023, at 12PM					
ATTACHMENTS	Draft SD Booklet					

# **CITY OF SUN PRAIRIE** SUN PRAIRIE PUBLIC LIBRARY **REMODEL AND ADDITION 1350 LINNERUD DRIVE** SUN PRAIRIE, WI

# **ISSUED FOR: SCHEMATIC DESIGN**



CONTACT INFORMATION

ARCHITECT FEH DESIGN 951 MAIN STREET DUBUQUE, IOWA 52001 PH: (563)583-4900

### **STRUCTURAL** FEH DESIGN 951 MAIN STREET DUBUQUE, IOWA 52001

PH: (563)583-4900

MECHANICAL DESIGN ENGINEERS 8215 GREENWAY BLVD SUITE 180 MADISON, WI 53717

PH: (608)424-8815

**ELECTRICAL** DESIGN ENGINEERS 8215 GREENWAY BLVD SUITE 180 MADISON, WI 53717 PH: (608)424-8815

CIVIL SNYDER AND ASSOCIATE 5010 VOGES ROAD MADISON, WI 53718

PH: (608)838-0444

AD1.0 A1.1 DEMOLITION PLANS FLOOR PLAN ROOF PLAN

GENERA TS AG1.1 AG1.2

CIVIL C100 C200 C300 C400 C401 C500

LANDSCAPE L100 L200 L300 L301

ARCHITECTURAL

A2.1 A4.1 A5.1 A7.0 A8.1 EXTERIOR ELEVATIONS

BUILDING SECTIONS 3D VIEWS REFLECTED CEILING PLANS

A10.1 FURNITURE LAYOUT PLANS

TITLE SHEET

GRADING PLAN UTILITY PLAN MISC. DETAILS

LANDSCAPE NOTES

PLANTING PLAN HARDSCAPE PLAN

HARDSCAPE PLAN

NOTES

GENERAL NOTES AND LEGENDS BUILDING CODE PLAN

EXISTING SITE & DEMO PLAN PROPOSED SITE

HVAC HVAC-A1.1 HVAC LAYOUT - FLOOR PLAN

HVAC-A2.1 HVAC LAYOUT - ROOF PLAN

ELECTRICAL SCHEMATIC POWER DISTRIBUTION CONCEP E1





	OCCUPANCY LOAD SCHEDULE							OCCUPANCY LOAD SCHEDULE						
NUMBER	NAME	FUNCTION OF SPACE	AREA	OCCUPANT LOAD FACTOR	OCCUPANT LOAD	OCCUPANT LOAD FOR PLUMBING CALCULATION	NUMBER	NAME	FUNCTION OF SPACE	AREA	OCCUPANT LOAD FACTOR	OCCUPANT LOAD	OCCUPANT LOAD FO PLUMBING CALCULAT	
1000	ARCADE	ASSEMBLY	1478 SF	15	99		1052	TEEN	LIBRARY STACKS	2438 SF	100	25		
1001	LOBBY	CIRCULATION	890 SF	0			1053	TOILET	TOILET	43 SF	0			
1002	LOBBY	CIRCULATION	219 SF	0			1054	TOILET	TOILET	48 SF	0			
1003	WOMEN'S	TOILET	167 SF	0			1055	ADULT COLLECTION	LIBRARY STACKS	11902 SF	100	120		
1004	MEN'S	TOILET	172 SF	0			1056	ASK	BUSINESS	360 SF	100	4		
1005	COMMUNITY	ASSEMBLY	1397 SF	7	200		1057	DISCUSS	ASSEMBLY	220 SF	15	15		
1006	STORAGE	STORAGE	59 SF	300	1		1058	RENK ROOM	LIBRARY READING	1387 SF	50	28		
1007	TABLE AND CHAIR STORAGE	STORAGE	274 SF	300	1		1059	LOCAL HISTORY	BUSINESS	118 SF	100	2		
1008	KITCHEN	KITCHEN	184 SF	200	1		1060	STUDY	ASSEMBLY	109 SF	15	8		
1008A	IT	STORAGE	38 SF	300	1		1061	STUDY	ASSEMBLY	61 SF	15	5		
1009	STORAGE	STORAGE	116 SF	300	1		1062	STUDY	ASSEMBLY	63 SF	15	5		
1010	MEETING	ASSEMBLY	497 SF	15	34		1063	STUDY	ASSEMBLY	61 SF	15	5		
1011	STUDIO	EDUCATIONAL VOCATIONAL	857 SF	50	18		1064	REFERENCE	BUSINESS	335 SF	100	4		
1012	EDITING	EDUCATIONAL VOCATIONAL	119 SF	50	3		1065	COMPUTERS	EDUCATIONAL VOCATIONAL	1077 SF	50	22		
1013	SUPPLY	STORAGE	183 SF	300	1		1066	STOR	STORAGE	40 SF	300	1		
1014	STUDIO	EDUCATIONAL VOCATIONAL	287 SF	50	6		1067	ADULT STAFF	OFFICE	424 SF	100	5		
1015	RADIO	EDUCATIONAL VOCATIONAL	93 SF	50	2		1068	ADULT SERV, OFFICE	OFFICE	154 SF	100	2		
1016	STAFF WORK	OFFICE	416 SF	100	5		1069	TOILET		56 SF				
1017	TOILET	TOILET	52 SF	0			1070	MAINTENANCE OFFICE	OFFICE	188 SF	100	2		
1018	SERVER	STORAGE	102 SF	300	1		1071	READY ROOM	ASSEMBLY	126 SF	300	1		
1019	OFFICE	OFFICE	99 SF	100	1		1072	READY ROOM	ASSEMBLY	132 SF	300	1		
1020	RADIO	EDUCATIONAL VOCATIONAL	94 SF	50	2		1073	т	TOILET	61 SF	0			
1021	STUDIO	EDUCATIONAL VOCATIONAL	185 SF	50	4		1074	T	TOILET	60 SF	0			
1022	STUDIO	EDUCATIONAL VOCATIONAL	254 SF	50	6		1075	ST	STORAGE	27 SF	300	1		
1023	EDITING	EDUCATIONAL VOCATIONAL	298 SF	50	6		1076	CORR	CIRCULATION	92 SF	0			
1024	MAKERSPACE	EDUCATIONAL VOCATIONAL	1306 SF	50	27		1077	RECEIVING	STORAGE	227 SF	300	1		
1025	CONFERENCE	ASSEMBLY	184 SF	15	13		1078	MAIL / COPY	BUSINESS	156 SF	100	2		
1026	STORAGE	STORAGE	274 SF	300	1		1079	TECH SERVICES	OFFICE	1177 SF	100	12		
1027	OFFICE	OFFICE	142 SF	100	2		1080	TECH SERV. OFFICE	OFFICE	112 SF	100	2		
1028	DISCUSS	ASSEMBLY	192 SF	15	13		1081	TECH COORD, OFFICE	OFFICE	117 SF	100	2		
1029	CHILDREN'S ENTRY	LIBRARY READING	573 SF	50	12		1082	SERVER	STORAGE	135 SF	300	1		
1030	STUDY	ASSEMBLY	158 SF	15	11		1083	FDN OFFICE	OFFICE	151 SF	100	2		
1031	SENSORY	ASSEMBLY	126 SF	15	9		1084	DIRECTOR OFFICE	ASSEMBLY	162 SF	15	11		
1032	JANITOR	STORAGE	370 SF	300	2		1085	ADMIN	OFFICE	99 SF	100	1		
1033	TOILET	TOILET	58 SF	0			1086	HUDDLE	OFFICE	114 SF	100	2		
1034	TOILET	TOILET	58 SF	0			1087	TOILET		59 SF				
1035	TOILET	TOILET	57 SF	0			1088	STAFF BREAK AREA	ASSEMBLY	393 SF	15	27		
1036	CAREGIVER ROOM	BUSINESS	111 SF	100	2		1089	STORAGE	STORAGE	14 SF	300	1		
1037	PRESCHOOL	LIBRARY STACKS	4570 SF	100	46		1090	PICK UP WINDOW	BUSINESS	62 SF	100	1		
1038	STORAGE	STORAGE	104 SF	300	1		1091	BOOK DROP	STORAGE	47 SF	300	1		
1039	VEST	CIRCULATION	106 SF	0			1092	VEST		70 SF				
1040	YOUTH PROGRAM ROOM	ASSEMBLY	1045 SF	7	150		1093	CIRC OFFICE	OFFICE	111 SF	100	2		
1041	MECHANICAL	STORAGE	766 SF	300	3		1094	WELLNESS	BUSINESS	77 SF	100	1		
1042	STORAGE	STORAGE	147 SF	300	1		1095	READ BEFORE BOOK STORE AND	LIBRARY READING	882 SF	50	18		
1043	READY ROOM	OFFICE	114 SF	100	2			CAFE					1	
1044	STAFF WKRM	OFFICE	768 SF	100	8		1096	READ BEFORE STORAGE	STORAGE	257 SF	300	1		
1045	OFFICE	OFFICE	140 SF	100	2		1097	MECHANICAL	STORAGE	457 SF	300	2		
1046	GRADESCHOOL	LIBRARY STACKS	4156 SF	100	42		1098	LOBBY	CIRCULATION	1070 SF	0			
1047	CHILDREN'S CIRC	BUSINESS	315 SF	100	4		1100	CIRCULATION	CIRCULATION	216 SF	0			
1048	CHILDREN'S COMPUTERS	LIBRARY READING	843 SF	50	17		1101	CIRCULATION	CIRCULATION	208 SF	0			
1049	DISCUSS	ASSEMBLY	153 SF	15	11		1102	CIRCULATION	CIRCULATION	1745 SF	0			
1050	DISCUSS	ASSEMBLY	157 SF	15	11		1104	CIRCULATION	CIRCULATION	490 SF	0			
									La muna m					



















		FEHDESIGN.COM
	FI SIOUX CITY, IA SIOUX CITY, IA DES MONUES, (712) 222-3889 (515) 289-2000	© FEH DESIGN
IT USED	IN ASSOCIATION WITH <b>EAST SOCIATES</b> <b>EAST SOCIATES</b> SOL VOIGE RU MONISSOL VII 35716 (B08) B385-0444 WWW.SNVDERASSOCIATESCOM	
	MISC. DETAILS	
IT USED		
	SUN PRARIE, WISCONSIN SUN PRARIE, WISCONSIN TATE ISTORY	
	PROJECT NUMBER 123.0502.30 SHEET	
IT USED	C 500	

#### GENERAL LANDSCAPE NOTES

- UTILITY WARNING: THE UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND/OR RECORDS OBTAINED. THE SURVEYOR MAKES IN GURARATIEE THAT THE UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA. ETHER IN SERVICE OR ABANDONED THE SURVEY FURTHER DOES NOT WARRANT THAT THE UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED.
- NOTIFY UTILITY OWNERS PROR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR DETERMINING EXISTENCE, EXACT LOCATION AND DEPTH OF ALL UTILITES AVOID DAMAGE TO UTILITES AND SERVICES DURING CONSTRUCTION. ANY DAMAGE DUE TO THE CONTRACTOR'S CARELESSMESS SHALL BE CORRECTED AT THE CONTRACTOR'S CARELESSMESS THALL BE CORRECTED AT THE CONTRACTOR'S DEVENSE. COORDINATE AND COOPERATE WITH UTILITY COMPARIES DURING CONSTRUCTION.
- 3. THE CONTRACTOR SHALL FOLLOW THE LANDSCAPE PLANS AS CLOSELY AS POSSIBLE. ANY SUBSTITUTION OR ALTERATION SHALL NOT BE ALLOWED WITHOUT APPROVAL OF THE OWNER'S REPRESENTATIVE. OVERALL PLANT QUANTITY AND QUALITY SHALL BE CONSISTENT WITH THE PLANS.
- 4. ALL PLANT MATERIAL SHALL AT LEAST MEET MINIMUM REQUIREMENTS SHOWN IN THE "AMERICAN STANDARDS FOR NURSERY STOCK" (ANSI Z60.1-LATEST EDITION).
- 5. MULCH SHALL NOT BE PLACED AROUND THE COLLAR OF SHRUB OR TREE. PROVIDE A MINIMUM OF 2" BETWEEN MULCH AND COLLAR OF SHRUB OR TREE
- ALL PLANT MATERIAL SHALL BE GROWN IN ZONE CAPABLE OF WITHSTANDING LOCAL CLIMATE AND GROWING CONDITIONS.
- 7. TREE OR SHRUB SHALL STAND PLUMB. DO NOT ALLOW AIR POCKETS TO FORM WHEN BACK FILLING.
- 8. LIVE PLANTS CAN BE PLANTED IN THE FIELD DURING THE GROWING SEASON FROM MAY 1 THROUGH OCTOBER 1. ANY SUGGESTED PLANTING TIME'S NOT IN THIS WINDOW SHALL BE APPROVED BY LANDSCAPE ARCHITECT. IF PLANTING OCCURS OUTSIDE OF THIS WINDOW, ADDITIONAL MEASURES MAY NEED TO BE TAKEN (IE. MUICH) TO FORUBE PLANT SURVIVAL. IN THESE INSTANCES, THE CONTRACT PRICE MAY NEED TO BE ADJUSTED ACCORDINGLY.
- 9. PLANTS SHOULD BE WATERED IN AFTER INSTALLATION TO ENSURE THEIR PLAN IS SHOULD BE WAITERED IN AFTER INSTALLATION TO ENSURE THEM SURVIVAL. THIS TYPICALLY INVOLVES WATERING AT THE OF INSTALLATION AND 2 TIMES WEEKLY FOR A ONE MONTH PERIOD OR VATILATION AND 2 TIMES WEEKLY FOR A ONE MONTH PERIOD OR VATILATION WATERING EVENT INVOLVES WATERING THE SOL IN THE PLANTED AREAS TO THE POINT OF SATURATION BUT STOPPING SHORT OF SOL DEPLACEMENT, SHOLLO VERY ORT CONDITIONS DEVELOP WITHIN ON ME DEPLACEMENT, SHOLLO VERY ORT CONDITIONS DEVELOP WITHIN ON ME DEPLACEMENT, SHOLLO VERY ORT CONDITIONS DEVELOP WITHIN ON ME DEPLACEMENT, SHOLLO VERY ORT CONDITIONS DEVELOP WITHIN ON ME DEPLACEMENT, SHOLLO VERY ORT CONDITIONS DEVELOP WITHIN ON ME DEPLACEMENT, SHOLLO VERY DEVELOP VERY ORT OF SOL CONTRACT FROM SOLVERY ORT CONDITIONS DEVELOP WITHIN THIS AND
- 10. ALL PLANT MATERIAL SHALL BE SPECIMEN QUALITY, HEALTHY, FREE OF DISEASE AND INSECTS AND SHALL HAVE HEALTHY, WELL-DEVELOPED ROOT SYSTEMS, PLANTS SHALL ALSO BE FREE FROM PHYSICAL DAMAGE OR OTHER CONDITIONS THAT WOULD PREVENT VIGOROUS GROWTH.
- 11. ALL PROPOSED PLANTS SHALL BE LOCATED AS SHOWN ON PLANS. ALL TREES TO BE PLANTED A MINIMUM DISTANCE OF 5 FEET FROM PAVEMENTS AND 6 FEET FROM ALL HYDRANTS.
- 12. CONTRACTOR IS RESPONSIBLE FOR PLANTS AWAITING INSTALLATION AND SHALL PROTECT THEM FROM INJURY AND THEFT.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL PLANT QUANTITIES. GRAPHIC QUANTITIES TAKES PRECEDENCE OVER WRITTEN QUANTITIES.
- 14 THE OWNER'S REPRESENTATIVE RESERVES THE RIGHT TO INSPECT AND THE OWNER'S REPRESENTATIVE RESERVES THE RIGHT TO INSPECT AND TAG ALL PLANT MATERIAL PRIOR TO SHIPPING TO THE STIE. INAL CASES, THE OWNER'S REPRESENTATIVE MAY REJECT PLANT MATERIAL AT THE STIE IF MATERIAL IS DAMAGED, DISEASED, OR SOLCIMING IN HEALTH AT THE TIME OF ONSTIE INSPECTIONS OR IF THE PLANT MATERIAL DOES NOT MEET THE MINUM SPECIFIED STANDARD IDENTIFIED ON THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE OWNER'S REPRESENTATIVE FOR INSPECTION AND APPROVAL OF ALL MATERIALS AND PRODUCTS PRIOR TO INSTALLATION.
- 15. THE OWNER'S REPRESENTATIVE MAY ELECT TO UPSIZE PLANT MATERIAL THE OWNER'S REPRESENTATIVE MAY ELECT TO UPSIZE PLANT MATERIAL AT THEIR DISCRETION BASED ON SELECTION, NALABILITY, OR TO ENHANCE SPECIFIC AREAS OF THE PROJECT. THE CONTRACTOR SHALL VERICY PLANT MATERIAL 3225 WITH OWNER'S REPRESENTATIVE FOR TO PURCHASING, SHIPPING OR STOCKING OF PLANT MATERIALS. SUBMIT CHANGE GREER REQUEST TO OWNER'S REPRESENTATIVE FOR APPROVA (F ADDITIONAL COST IS REQUESTED BY THE CONTRACTOR PRIOR TO INSTALLATION RE-STOCKING CHARGES WILL NOT BE APPROVED IF THE CONTRACTOR FAILS TO SUBMIT A REQUEST FOR MATERIAL CHANGES.
- 16. THE CONTRACTOR SHALL WARRANTY ALL CONTRACTED WORK AND MATERIALS FOR A PERIOD OF ONE YEAR AFTER SUBSTANTIAL COMPLETION HAS BEEN ISSUED BY THE OWNER'S REPRESENTATIVE FOR THE ENTIRE PROJECT UNLESS OTHERWISE SPECIFIED IN THE CONTRACT
- 17. LANDSCAPE MATERIAL LOCATIONS SHALL HAVE PRECEDENCE OVER IRRIGATION MAINLINE AND LATERAL LOCATIONS. IF IRRIGATION IS INCLUDED, COORDINATE INSTALLATION OF IRRIGATION EQUIPMENT SO THAT IT DOES NOT INTERFERE WITH THE PLANTING OF TREES OR OTHER LANDSCAPE MATERIA
- IS THE LANGEAPE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING POSITIVE DRAINAGE EXISTS IN ALL LANDSCAPE AREAS. SURFACE DRAINAGE ON LANDSCAPE REASS SHALL AND TAND TO FLOW TOWARD STRUCTURES AND FOUNDATIONS. MAINTAIN SLOPE AWAY FROM FOUNDATIONS PERT HIE GEOTECHNICAL REPORT RECOMMENDATIONS. ALL LANDSCAPE AREAS BETWEEN WALKS AND CURBS SHALL DRAIN FREELY TO THE CURB UNLESS OTHERWINGS DENTIFIED ON THE GRADING FLAN. IN NO CASE SHALL THE GRADE, TURF THATCH, OR OTHER LANDSCAPE MATERILAS DAM WATER AGAINST WALKS. MINIMUM SLOPE SHALL BE 25% UNLESS SPECIFICALLY IDENTIFIED ON THE PLANS OR APPROVED BY THE OWNER'S REPRESENTATIVE.
- 19. PRIOR TO INSTALLATION OF PLANT MATERIALS, AREAS THAT HAVE BEEN COMPACTED OR DISTURBED BY CONSTRUCTION ACTIVITY SHALL BE THOROUGHLY LOOSENED TO A DEPTH OF 8" 12".
- 20. ALL LANDSCAPED AREAS ARE TO RECEIVE ORGANIC SOIL PREPARATION PER RATE IDENTIFIED BY A SOIL TEST.
- 21. TREES SHALL NOT BE LOCATED IN DRAINAGE SWALES, DRAINAGE AREAS, OR UTILITY EASEMENTS. CONTACT OWNER'S REPRESENTATIVE FOR RELOCATION OF PLANTS IN QUESTIONABLE AREAS PRIOR TO INSTALLATION
- 22. THE CENTER OF EVERGREEN TREES SHALL NOT BE PLACED CLOSER THAN 8' AND THE CENTER OF ORNAMENTAL TREES CLOSER THAN 6' FROM A SIDEWALK. STREET OR ORNE CLARE. EVERGENT TREES BALL NOT BE LOCATED ANY CLOSER THAN 15' FROM IRRIGATION ROTOR HEADS. NOTIFY OWNER'S REPRESENTATIVE IF TREE LOCATIONS CONFLICT WITH THESE STANDARDS FOR FURTHER DIRECTION.
- ALL EVERGREEN TREES SHALL BE FULLY BRANCHED TO THE GROUND AND SHALL NOT EXHIBIT SIGNS OF ACCELERATED GROWTH AS DETERMINED BY THE OWNER'S REPRESENTATIVE
- 24. ALL TREES ARE TO BE STAKED AND GUYED PER DETAILS FOR A PERIOD OF 1YEAR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING STAKES AT THE END OF YEAR RFOM ACCEPTIANCE OF LANDSCAPE INSTALLATION BY THE OWNER'S REPRESENTATIVE. OBTAIN APPROVAL BY OWNER'S REPRESENTATIVE PRIOR TO REMOVAL.
- 25. ALL TREES INSTALLED ABOVE RETAINING WALLS UTILIZING GEO-GRID MUST BE HAND DUG TO PROTECT GEO-GRID. IF GEO-GRID MUST BE CUT TO INSTAL TREES, APPROVAL MUST BE GIVEN BY OWNER'S REPRESENTATIVE PRIOR TO DOING WORK.
- 26. ALL TREES IN SEED OR TURF AREAS SHALL RECEIVE MULCH RINGS. OBTAIN APPROVAL FROM OWNER'S REPRESENTATIVE FOR ANY TREES THAT WILL NOT BE MULCHED FOR EXCESSIVE MOISTURE REASONS.
- 27. EXISTING TURF AREAS THAT ARE DISTURBED DURING CONSTRUCTION ESTABLISHMENT AND THE MAINTENANCE PERIOD SHALL BE RESTORE WITH NEW SOD TO MATCH EXISTING TURE SPECIES. DISTURBED NATIVE AREAS WHICH ARE TO REMAIN SHALL BE OVER SEEDED AND RESTORED WITH SPECIFIED SEED MIX.
- WHEN COMPLETE, ALL GRADES SHALL BE WITHIN +/- 1/8" OF FINISHED GRADES AS SHOWN ON THE PLANS.

- 29. WHEN PLANTER POTS ARE SHOWN ON PLANS, CONTRACTOR SHALL INCLUDE THE FOLLOWING: PLANTER MIX, ANNUAL FLOWER PLANTING PROGRAM (INCLUDES 2 PLANTING FOR THE IST YEAR, (SPING AND FALL) AND WINTER HAND-WATERING AS NEEDED. UNLESS OTHERWISE SPECIFIED, CONTRACTOR TO PROVIDE ANNUAL PLANTING SELECTION FOR REVIEW BY OWNER, IRRIGATION FOR PLANTERS TO BE ON SEPARATE 2004(S): CONTRACTOR TO COORDINATE PLACEMENT OF NECESSARY SLEEVING PRIOR TO PLACEMENT OF PAVEMENT.
- 30. PRIOR TO THE PLACEMENT OF MULCH AND WEED FABRIC, A GRANULAR, PRE-EMERGENT, WEED CONTROL AGENT SHALL BE ADDED TO ALL PLANTING BEDS IN ACCORDANCE WITH THE MANUFACTURE'S INSTRUCTION, EXCEPT AROUND ORNAMENTAL GRASSES.
- 31. THE CONTRACTOR IS EXPECTED TO KNOW AND UNDERSTAND THE CITY AND COUNTY SPECIFICATIONS FOR LANDSCAPE AND IRRIGATION. IN CASES OF DISCREPANCIES THE HIGHER OF THE TWO STANDARDS SHALL HAVE PRECEDENCE.
- ALL TREES PLANTED WITHIN RIGHT-OF-WAY WILL INCLUDE CITY APPROVED ROOT BARRIERS.

































ASK DESK



ATRIUM







VIEW FROM YOUTH ENTRANCE

COMPUTERS AND REFERENCE DESK



YOUTH ENTRANCE

















# CONTACT:

### FEH DESIGN

1241 CORPORATE CENTER DRIVE OCONOMOWOC, WI 53066 262 968 2055

WWW.FEHDESIGN.COM

